

BRIDGE JOINT SCHEDULE

BRIDGE	JOINT	REINFORCEMENT BARS - EPOXY CTD. (POUND)	CONCRETE REMOVAL (CU YD)	CONCRETE SUPERSTRUCTURE (CU YD)	BAR SPLICERS (EACH)	PREFORM JT. STRIP SEAL (FOOT)	MECHANICAL SPLICE (EACH)	STRUCTURAL STEEL REM. (POUND)	FURNISH & ERECT STRUCTURAL STEEL (POUND)	FINGER PLATE EXPANSION JT., 3" (FOOT)	FABRIC REINFORCED ELASTOMERIC TROUGH (FOOT)
065-0002	N. ABUT.	571.2	4.4	4.9	11	37.2					
065-0002	BENT 4	856.6	4.6	5.6	16	37.2					
065-0002	PIER 7	856.6	4.6	5.6	16	37.2					
065-0002	S. ABUT	571.2	4.4	4.9	11	37.2					
065-0003	PIER 3	1317.1	9.4	9.9	22		70	895	605	32	37
065-0003	PIER 6	856.6	4.6	5.6	16	37.2					
065-0003	PIER 9	1317.1	9.4	9.9	22		70	895	605	32	37
	TOTALS	6346	41.4	46.4	114	186	140	1790	1210	64	74

MISCELLANEOUS BRIDGE ITEM SCHEDULE

BRIDGE	BRIDGE DECK GROOVING (SQ YD)	CONCRETE SEALER (SQ FT)	INLETS TO BE ADJUSTED (EACH)	TEMP. CONC. BARRIER (FOOT)	POLYMER CONCRETE (CU FT)	BD MICROSILICA CONC. OVERLAY (SQ YD)	BD HYDRO-SCARIFICATION (SQ YD)	DECK SLAB REPAIR (FD, TY2) (SQ YD)	DRAINAGE SCUPPERS TO BE ADJUSTED (EACH)
065-0002	2430	21870	0	1050	0	2592	2592	5.4	0
065-0003	2657	23910	4	1125	2.9	2834	2834	47.6	16
	TOTALS	5087	4	2175	2.9	5426	5426	53	16

AGGREGATE SHOULDER SCHEDULE

STA	TO	STA	RIGHT SIDE AGGREGATE SHLDR. TY B (TON)	LEFT SIDE AGGREGATE SHLDR. TY B (TON)
723+00		726+56	8.1	8.1
734+25		751+81	40.0	40.0
760+18		765+70	12.6	12.6
		TOTALS	60.7	60.7

HMA BASE COURSE WIDENING SCHEDULE

STA	TO	STA	RIGHT SIDE		LEFT SIDE	
			WIDTH	HMA BASE CSE WIDENING 9" (SQ YD)	WIDTH	HMA BASE CSE WIDENING 9" (SQ YD)
723+00		724+50	1' TO 4'	41.7	1' TO 4'	41.7
724+50		726+76	4'	91.7	4'	91.7
734+05		736+30	4'	91.0	4'	91.0
736+30		737+80	4' TO 1'	41.7	4' TO 1'	41.7
747+62		749+12	1' TO 3'	33.3		
749+12		751+81	3'	89.9		
760+18		764+20	3'	133.8		
764+20		765+70	3' TO 1'	33.3		
		TOTALS		556.3		266.1

PAVEMENT MARKING SCHEDULE

STA	TO	STA	LOCATION	TYPE	COLOR	PAINT PAVT. MARK.-LINE 5" (FOOT)
723+00		765+70	LEFT EDGE	SOLID	WHITE	4270
723+00		765+70	RIGHT EDGE	SOLID	WHITE	4270
723+00		765+70	CENTERLINE	SKIP DASH	YELLOW	1068
		TOTAL				9608

SCHEDULES OF QUANTITIES
FAP 34 (IL 97)
SECTION (2) BRIDGE REHAB
MENARD COUNTY