

**ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES**

LOCATION OF WORK				90% FED			
SUMMARY OF QUANTITIES				10% STATE			
PAY CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000			
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	217.8	217.8			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	936.9	936.9			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	7,318.9	7,318.9			
64200105	SHOULDER RUMBLE STRIP	FOOT	24,689.9	24,689.9			
67100100	MOBILIZATION	L SUM	1.0	1.0			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0			
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15.0	15.0			
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	21,773.6	21,773.6			
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	21,773.6	21,773.6			

**SPECIALTY ITEMS*

FILE NAME =	USER NAME = laughlrm1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ct:\pw\work\PWIDOT\LAUGHLINRL\d0136657	72e97-ahtr-soq.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	608	122, 125, 126, INT-SHLD	MACOUPIN	15	3
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		CONTRACT NO. 72C97										
	PLOT DATE = Oct-13-2009 10:20:19AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT										