

COUNTY	LOCATION #	PREFORMED	PREFORMED	PREFORMED	PREFORMED	PREFORMED	PREFORMED	PREFORMED	PREFORMED	URETHANE	URETHANE	URETHANE	URETHANE	URETHANE	PVT MRK
		LET & SYM (SQ FT)	LINE 24 (FOOT)	THERMO LET & SYM (SQ FT)	THERMO LINE 5 (FOOT)	THERMO LINE 6 (FOOT)	THERMO LINE 8 (FOOT)	THERMO LINE 12 (FOOT)	THERMO LINE 24 (FOOT)	LET & SYM (SQ FT)	LINE 5 (FOOT)	LINE 6 (FOOT)	LINE 8 (FOOT)	LINE 12 (FOOT)	REMOVAL (SQ FT)
SANGAMON	11 *			31.2	320	320	80	40	24						262.4
	12 *		16												
	13 *		24												48
	14 *		36												72
	15 *														
	16 *	31.2													
	17 *	31.2													
	25 *	121													
	26 (Deleted)														
	27 (Deleted)														
	28 (Deleted)														
	29 (Deleted)														
	30 *	150													
	31 *	121													
	32 *	121													
	33 *	98													
	34 *	49													
	35 *	49													
	36 *	121													
	37 *	121													
	38 *	150													
	39 *	150													
	51 *				83										
	52 *				83										
	53 *				83										
54 *				83											
55 *				83											
60													677		
70										97.2					
71 *										97.2					
72 *										97.2					
73										97.2					
74										97.2					
SCHUYLER	18	199.2													
	58	83													
SCOTT	65								97.2						
TOTALS		2766.8	102	1442.2	320	320	80	40	24	2166	80	671	811	1401	382.4

Locations with an asterisk (\*) are within Springfield-Sangamon County MP0.

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
e:\pwwork\pwidot\LAUGHLINRL\0150723\0672C99-sht-schedule.dgn	DRAWN -	REVISED -			VAR	D6 PAVT MARKING 2010	VARIOUS	37	8				
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 72C99				
PLOT DATE = Oct-22-2009 09:18:05AM	DATE -	REVISED -			ILLINOIS FED. AID PROJECT								