

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	0.75
20200100	EARTH EXCAVATION	CU YD	4,930
20300100	CHANNEL EXCAVATION	CU YD	674
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	150
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.50
25100630	EROSION CONTROL BLANKET	SQ YD	230
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	139
28000305	TEMPORARY DITCH CHECKS	FOOT	150
28000500	INLET AND PIPE PROTECTION	EACH	1
28000400	PERIMETER EROSION BARRIER	FOOT	613
28100105	STONE RIPRAP, CLASS A3	SQ YD	74
28100109	STONE RIPRAP, CLASS A5	SQ YD	752
28200200	FILTER FABRIC	SQ YD	826
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	365
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	464
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	58
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	802
40600300	AGGREGATE (PRIME COAT)	TON	17
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160
40600990	TEMPORARY RAMP	SQ YD	85
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	574
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	188
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	57
44000100	PAVEMENT REMOVAL	SQ YD	332
44004250	PAVED SHOULDER REMOVAL	SQ YD	143
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	195
48203100	HOT-MIX ASPHALT SHOULDERS	TON	841
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50105220	PIPE CULVERT REMOVAL	FOOT	30
50200100	STRUCTURE EXCAVATION	CU YD	229
50300100	FLOOR DRAINS	EACH	12
50300225	CONCRETE STRUCTURES	CU YD	72.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	270.3
50300260	BRIDGE DECK GROOVING	SQ YD	594
50300280	CONCRETE ENCASEMENT	CU YD	4.2
50300300	PROTECTIVE COAT	SQ YD	723
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	2,256
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	68,750

/4915/4915.195A#3LucasCreekStandalone/smg45_01.dgn

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - DJR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 328	SECTION 4(BR-1)B	COUNTY CLAY	TOTAL SHEETS 42	SHEET NO. 3		
PLOT SCALE = #SCALE#	CHECKED -	REVISOR -	SCALE:			SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 74310			
PLOT DATE = #DATE#	DATE -	REVISED -	ILLINOIS FED. AID PROJECT									

SHEET NO. 4915