

**SUMMARY OF QUANTITIES**

80% FED.  
20% STATE

CODE NO.	ITEM	UNIT	X071-2A QUANTITY
50800515	BAR SPLICERS	EACH	575
51201700	FURNISHING STEEL PILES HP12X74	FOOT	216
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	32
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	74
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4
60100905	PIPE DRAINS 4"	FOOT	38
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	155
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6" POSTS	FOOT	837.5
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	476
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	12
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
<del>70100500</del>	<del>TEMPORARY BRIDGE TRAFFIC SIGNALS</del>	<del>EACH</del>	<del>1</del>
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	480
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	716
70400100	TEMPORARY CONCRETE BARRIER	FOOT	637.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	612.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,160
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	19
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	13
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	368
X0326372	REMOVE RIGHT-OF-WAY MARKERS	EACH	2
<del>X0006733</del>	<del>TOPSOIL EXCAVATION AND PLACEMENT, 4"</del>	<del>SQ YD</del>	<del>3,695</del>
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
* Z0065000	SETTING PILES IN ROCK	EACH	12

\*Specialty Items

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - DJR	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 328	SECTION 4(BR-1)B	COUNTY CLAY	TOTAL SHEETS 42	SHEET NO. 4		
PLOT SCALE = #SCALE#	CHECKED -	REVISED -	REVISED -			SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 74310		
PLOT DATE = #DATE#	DATE -	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT						
HENRY, MEISENHEIMER & GENDE, INC., 1075 LAKE ROAD, PO BOX 70, CARLYLE, IL 62231 PHONE (618) 594-3711 WWW.HMGENGINEERS.COM												

Rev.  
H.M.G. NO. 4915