

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	TEMPORARY PAVEMENT MARKING - LINE 4"	WORKZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	PAINT PAVEMENT MARKING - LINE 4"	
						WHITE (SOLID)	YELLOW (SKIP-DASH)
STATION		FOOT	SQ FT	EACH	EACH	FOOT	FOOT
FAP RTE 328 (US RTE 45)							
LT STA 807+40 TO 817+00				12.0	1.0	960.0	240.0
CTR STA 807+40 TO 817+00						960.0	
RT STA 807+40 TO 817+00							
STAGE 1							
STA 808+21 TO 816+62	SOLID		98.8				
STA 808+61 (FOR STAGE 1 & 2)	SOLID		24.0				
STA 816+50 (FOR STAGE 1 & 2)	SOLID		24.0				
STAGE 2							
STA 807+85 TO 816+40	SOLID		285.6				
STA 809+36 TO 815+44	SOLID		202.8				
BEFORE APPLICATION OF HMA SURFACE							
** CTR STA 807+40 TO 817+00	SKIP - DASH	240.0					
*** CTR STA 807+40 TO 817+00	SKIP - DASH	240.0	80.0				
TOTAL		480.0	715.2	12.0	1.0	1920.0	240.0
USE		480	716	12	1	1920	240

** - TEMPORARY PAVEMENT MARKING, 4" SHOULD BE PAINT. IT WILL NOT BE APPLIED TO THE FINAL SURFACE, BUT IMMEDIATELY AFTER THE LAST LIFT OF BINDER COURSE.
 *** - TEMPORARY PAVEMENT MARKING, 4" SHOULD BE TAPE. IT WILL BE APPLIED TO THE FINAL SURFACE, AND THEN REMOVED IMMEDIATELY PRIOR TO THE FINAL PAVEMENT MARKINGS.

SEEDING SCHEDULE

LOCATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 2 (SPECIAL)
STATION	POUND	ACRE
FAP RTE 328 (US RTE 45)		
LT STA 806+98 TO 808+00	5.16	0.05
RT STA 806+98 TO 808+00	3.64	0.04
LT STA 808+00 TO 809+00	5.04	0.05
RT STA 808+00 TO 809+00	6.41	0.06
LT STA 809+00 TO 810+00	2.61	0.03
RT STA 809+00 TO 810+00	6.11	0.06
LT STA 810+00 TO 811+00	2.36	0.02
RT STA 810+00 TO 811+00	6.93	0.07
LT STA 811+00 TO 812+70	4.57	0.05
RT STA 811+00 TO 812+70	11.15	0.11
LT STA 812+70 TO 814+00	10.33	0.10
RT STA 812+70 TO 814+00	7.28	0.07
LT STA 814+00 TO 815+00	15.91	0.16
RT STA 814+00 TO 815+00	7.57	0.08
LT STA 815+00 TO 816+00	18.30	0.18
RT STA 815+00 TO 816+00	5.13	0.05
LT STA 816+00 TO 817+50	16.82	0.17
RT STA 816+00 TO 817+50	3.19	0.03
TOTAL	138.51	1.38
USE	139	1.50

/4915/4915.195A*3\LucasCreekStandalone/sch45_01.dgn

FILE NAME =	USER NAME = *USER*	DESIGNED - DJR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - KOJ	REVISED -			328	4(BR-1)B	CLAY	42	10	
PLOT SCALE = *SCALE*		CHECKED -	REVISED -			CONTRACT NO. 74310					
PLOT DATE = *DATE*		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET NO. 4 OF 4 SHEETS	STA.	TO STA.				

PLG. NO. 4915