

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS / HIGHWAY STANDARDS / GENERAL NOTES / COMMITMENTS
3. SUMMARY OF QUANTITIES
4. TYPICAL SECTIONS, MIXTURE REQUIREMENTS, AND MISC. DETAILS
5. SCHEDULE OF QUANTITIES
6. PLAN SHEET
7. TRAFFIC CONTROL SIGNING PLAN
8. - 11. SUGGESTED STAGE I CONSTRUCTION & TRAFFIC CONTROL - NB
12. - 15. SUGGESTED STAGE II CONSTRUCTION & TRAFFIC CONTROL - NB
16. - 19. SUGGESTED STAGE I CONSTRUCTION & TRAFFIC CONTROL - SB
20. - 23. SUGGESTED STAGE II CONSTRUCTION & TRAFFIC CONTROL - SB
24. - 25. PAVEMENT MARKING DETAILS
26. - 45. STRUCTURE PLANS

HIGHWAY STANDARDS

- 000001-05
- 001001-02
- 001006
- 701400-04
- 701402-07
- 701406-05
- 701901-01
- 704001-06
- 780001-02
- 781001-03

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

- AMERENIP
- AMERENUE
- AT&T ILLINOIS
- VILLAGE OF CASEYVILLE
- CHARTER COMMUNICATION, INC.
- MEDIACOM LLC CENTRAL
- PAETEC/McLEOD USA TELECOMMUNICATIONS, INC
- MEDIACOM LLC CENTRAL
- QWEST SOLUTIONS CENTER

MEMBERS OF J.U.L.I.E (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.

4. A QUANTITY OF 9525 FEET OF "TEMPORARY PAVEMENT MARKING - LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
5. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS, HOWEVER, INSTALLATION BY METHOD "A" (ARTICLE 730.04(A)) SHALL BE THE ONLY METHOD PERMITTED.
6. TWO LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
7. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE REQUIRED AT INTERSECTING SIDE ROADS THROUGHOUT THE PROJECT. COST TO BE INCLUDED IN BID PRICES FOR TRAFFIC CONTROL AND PROTECTION.
8. IT IS THE CONTRACTOR'S OPTION TO USE THE MATERIAL TRANSFER DEVICE ON ANY LIFT. THE PAY ITEM FOR MATERIAL TRANSFER DEVICE WILL NOT BE INCLUDED IN THIS CONTRACT.

COMMITMENTS

NONE

FILE NAME =	USER NAME = gelnh	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS /HIGHWAY STANDARDS GENERAL NOTES /COMMITMENTS	F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\p\WIDOT\GELINH\d0116760\0876928-Plans.dgn	DRAWN -	REVISED -	255			82-1HVB-I-1	ST CLAIR	45	2	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 76926							
PLOT DATE = 10/6/2009	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET NO. 1 OF 1 SHEET		STA. TO STA.		