

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.6	1.6	
40600300	AGGREGATE (PRIME COAT)	TON	8	8	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	623	623	
40600990	TEMPORARY RAMP	SQ YD	249	249	
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	2524	2524	
45200300	JOINT OR CRACK FILLING	POUND	330	330	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	197	197	
50102400	CONCRETE REMOVAL	CU YD	171.7	171.7	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	164.1	164.1	
50300300	PROTECTIVE COAT	SQ YD	61	61	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5840	5840	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28	28	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	14780	14780	
50800515	BAR SPLICERS	EACH	144	144	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	289.5	289.5	
52000216	FINGER PLATE EXPANSION JOINT, 5"	FOOT	129	129	
52000220	FINGER PLATE EXPANSION JOINT, 6"	FOOT	410.5	410.5	
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	550	550	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14	14	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14	14	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	56	56	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	25800	25800	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18840	18840	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	53900	53900	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11100	11100	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24247	24247	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5550	5550	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5550	5550	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20415	20415	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	472	472	
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	392	392	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5863	5863	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	472	472	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	200	200	
X7010820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	L SUM	1	1	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	31	31	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	60	60	
Z0018800	DRAINAGE SYSTEM	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
@ 20076600	TRAINEES	HOURL	1,000	1,000	
	@ Y080				

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = gelinh	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 255	SECTION 82-1HVB-I-1	COUNTY ST CLAIR	TOTAL SHEETS 45	SHEET NO. 3
ca:\pw\work\puidot\gelinh\d0116760\0876926-Plans.dgn		DRAWN -	REVISED -							
PLOT SCALE = 50.0000 / IN.		CHECKED -	REVISED -							
PLOT DATE = 10/9/2009		DATE -	REVISED -		SCALE: _____	SHEET NO. 1 OF 1 SHEET	STA. _____	TO STA. _____	CONTRACT NO. 76926	
						FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				