

RESURFACING SCHEDULE

STATION			BITUMINOUS MATERIAL (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	HMA SURF. REMOVAL BUTT-JOINT (SQ-YD)	POLYM. HMA SURF. CSE., MIX "E" N105 (TON)	HMA SHOULDERS (TON)	
NORTH BOUND								
1165+00.00	TO	1166+50.00	RT	0.05	0.25		18.67	
1165+00.00	TO	1166+68.13	RT	0.21	1.01	75.32		
1165+00.00	TO	1166+86.25	RT	0.06	0.31		23.18	
1165+00.00	TO	1165+50.00	RT			311.11		
1166+61.49	TO	1188+51.03	BRIDGE			1083.60		
1188+29.64	TO	1190+00.00	RT	0.06	0.28		21.20	
1188+46.60	TO	1190+00.00	RT	0.19	0.92	68.72		
1188+63.57	TO	1190+00.00	RT	0.05	0.23		16.98	
SOUTH BOUND								
1165+00.00	TO	1167+65.08	LT	0.09	0.44		32.99	
1165+00.00	TO	1167+46.95	LT	0.31	1.48	110.63		
1165+00.00	TO	1167+28.82	LT	0.08	0.38		28.48	
1167+49.77	TO	1187+68.41	BRIDGE			1083.60		
1187+55.87	TO	1190+00.00	LT	0.08	0.41		30.38	
1187+72.84	TO	1190+00.00	LT	0.28	1.36	101.76		
1187+89.80	TO	1190+00.00	LT	0.07	0.34		25.01	
1189+50.00	TO	1190+00.00	LT			311.11		
TOTAL				1.55	7.41	622.22	2523.63	196.89

STAGE CONSTRUCTION SCHEDULE (NB)

LOCATION			TEMPORARY CONCRETE BARRIER (FT)	RELOCATE TEMPORARY CONCRETE BARRIER (FT)	IMPACT ATTENUATOR TEMPORARY (EA)	RELOCATE IMPACT ATTENUATOR (EA)
STAGE I - NB						
1162+46.50					1	
1162+46.50	TO	1164+83.50	237.50			
1164+83.50	TO	1190+08.50	2525.00			
STAGE II - NB						
1162+46.50						1
1162+46.50	TO	1164+83.50		237.5		
1164+83.50	TO	1190+08.50		2525.00		
TOTAL			2762.50	2762.50	1	1

STAGE CONSTRUCTION SCHEDULE (SB)

LOCATION			TEMPORARY CONCRETE BARRIER (FT)	RELOCATE TEMPORARY CONCRETE BARRIER (FT)	IMPACT ATTENUATOR TEMPORARY (EA)	RELOCATE IMPACT ATTENUATOR (EA)
STAGE I - SB						
1164+87.50	TO	1190+12.50	2525.00			
1190+12.50	TO	1192+75.00	262.50			
1192+75.00					1	
STAGE II - SB						
1164+87.50	TO	1190+12.50		2525.00		
1190+12.50	TO	1192+75.00		262.5		
1192+75.00						1
TOTAL			2787.50	2787.50	1	1

PAVEMENT MARKING SCHEDULE

STATION			4" WHITE LINE (FT)	YELLOW LINE 4" (FT)	RAISED REFLECTIVE PAVEMENT MARKER (EA)
NORTH BOUND					
1149+00.00	TO	1196+09.00	SKIP DASH	2354.50	236
1156+83.00	TO	1196+09.00	EDGE LINES	3926.00	3926.00
SOUTH BOUND					
1158+87.00	TO	1206+00.00	SKIP DASH	2356.50	236
1158+87.00	TO	1203+00.00	EDGE LINES	3926.00	3926.00
SUB-TOTAL				12563.00	7852.00
TOTAL				20415.00	472

PAVEMENT MARKING REMOVAL SCHEDULE

STATION			PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EA)
NB	1149+00.00	TO 1196+09.00	SKIP DASH	313.9
	1156+83.00	TO 1196+09.00	EDGE LINES	2617.3
SB	1158+87.00	TO 1198+13.00	EDGE LINES	2617.3
	1158+87.00	TO 1206+00.00	SKIP DASH	314.2
SUB-TOTAL				5862.7
TOTAL				472

TEMPORARY PAVEMENT MARKING SCHEDULE (NB)

STATION			PAVEMENT MARKING		SHORT TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKER (EA)
			LINE 4" PAVEMENT (FT)	LINE 6" (FT)			
STAGE I - NB							
1139+83.50	TO	1156+83.50	1700.00			566.67	
1156+83.50	TO	1196+08.50	EDGE LINES		3140.00	3663.33	
1156+83.50	TO	1196+08.50	CENTERLINE		1570.00	1831.67	98
1162+46.50	TO	1164+83.50	TEMP. BARR.	237.50			
1164+83.50	TO	1190+08.50	TEMP. BARR.	2525.00			
STAGE II - NB							
1139+83.50	TO	1156+83.50	1700.00			566.67	
1156+83.50	TO	1196+08.50	EDGE LINES		3140.00	3663.33	
1156+83.50	TO	1196+08.50	CENTERLINE		1570.00	1831.67	98
1162+46.50	TO	1164+83.50	TEMP. BARR.	237.50			
1164+83.50	TO	1190+08.50	TEMP. BARR.	2525.00			
SUB-TOTAL							
TOTAL			26950.00	5525.00	9420.00	12123.34	196

TEMPORARY PAVEMENT MARKING SCHEDULE (SB)

STATION			PAVEMENT MARKING		SHORT TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKER (EA)
			LINE 4" PAVEMENT (FT)	LINE 6" (FT)			
STAGE I - NB							
1158+87.50	TO	1198+12.50	EDGE LINES		3140.00	3663.33	
1158+87.50	TO	1198+12.50	CENTERLINE		1570.00	1831.67	98
1164+87.50	TO	1190+12.50	TEMP. BARR.	2525.00			
1190+12.50	TO	1192+75.00	TEMP. BARR.	262.50			
1198+12.50	TO	1215+12.50			1700.00	566.67	
STAGE II - SB							
1158+87.50	TO	1198+12.50	EDGE LINES		3140.00	3663.33	
1158+87.50	TO	1198+12.50	CENTERLINE		1570.00	1831.67	98
1164+87.50	TO	1190+12.50	TEMP. BARR.	2525.00			
1190+12.50	TO	1192+75.00	TEMP. BARR.	262.50			
1196+00.00	TO	1213+00.00			1700.00	566.67	
SUB-TOTAL							
TOTAL			26950.00	5575.00	9420.00	12123.34	196