

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKERS - DIRECT APPLIED
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
SOUTHBOUND							3	3	
NW QUADRANT	213.9	50	1		1	1			1
SW QUADRANT	151.1	25	1	1		1			1
NORTHBOUND							4	4	
NE QUADRANT	151.1	25	1	1					1
SE QUADRANT	213.9	62.5	1		1	1			1
TOTAL	730	162.5	4	2	2	3	7	7	4

PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL		SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING 4"		WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING -4"		POLYUREA PAVEMENT MARKING -4"		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	REPLACEMENT REFLECTOR			
	YELLOW	WHITE		YELLOW	WHITE		YELLOW	WHITE	YELLOW	WHITE							
	STATION TO	STATION	SQ FT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	
STA 683+00	TO STA. 684+00	6	48	12.4	18	144	58.1	18	144						1		
STA 684+00	TO STA. 685+00	8.3	66.7	17.1	25	200	80.7	25	200						1		
STA 685+00	TO STA. 686+00	8.3	66.7	17.1	25	200	80.7	25	200								
STA 686+00	TO STA. 687+00	8.3	66.7	17.1	25	200	80.7	11.1	88.8	14.1	111.4	1		1			
STA 687+00	TO STA. 688+00	8.3	66.7	17.1	25	200	80.7			25	200			1			
STA 688+00	TO STA. 689+00	8.3	66.7	17.1	25	200	80.7			25	200			1			
STA 689+00	TO STA. 690+00	8.3	66.7	17.1	25	200	80.7	17.7	140.4	7.6	59.9	2	1	1			
STA 690+00	TO STA. 691+00	8.3	66.7	17.1	25	200	80.7	25	200			1	1				
STA 691+00	TO STA. 692+00	8.3	66.7	17.1	25	200	80.7	25	200			1			1		
STA 692+00	TO STA. 693+00	6.7	53.3	13.8	20	160	64.6	20	160			1			1		
SUBTOTAL		79.1	634.9		238.0	1904.0		166.8	1333.2	71.7	571.3						
TOTAL			714	163		2142	768.3		1500		643			10	4	4	4

REPLACEMENT REFLECTORS (REMOVED DURING STAGE CONSTRUCTION) ARE FROM STA. 683+28 TO STA. 684+70 & STA. 691+05 TO STA. 692+80.
 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL REQUIRES ONLY THE REFLECTORS TO BE REMOVED IN THE AREA DEFINED FOR REPLACEMENT REFLECTORS.