

SUMMARY OF QUANTITIES

ST. CLAIR COUNTY

CODE NO.	ITEM	UNIT	URBAN		ROADWAY		CONSTRUCTION TYPE CODE											
			TOTAL QUANTITY	100% STATE	J000-2A													
20100500	TREE REMOVAL, ACRES	ACRE	0.04	0.04														
20200100	EARTH EXCAVATION	CU YD	10,524	10,524														
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	6,266	6,266														
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	769	769														
20800150	TRENCH BACKFILL	CU YD	1,428	1,428														
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	12,437	12,437														
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	13,072	13,072														
25000210	SEEDING, CLASS 2A	ACRE	6.0	6.0														
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	540	540														
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	540	540														
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	540	540														
25100115	MULCH, METHOD 2	ACRE	13.3	13.3														
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,924	2,924														
28000400	PERIMETER EROSION BARRIER	FOOT	9,956	9,956														
28000510	INLET FILTERS	EACH	84	84														
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	553	553														
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	249	249														
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	211	211														
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	59	59														
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	26	26														
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	264	264														
40800030	AGGREGATE (PRIME COAT)	TON	2	2														
42000541	PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)	SQ YD	9,650	9,650														
42001300	PROTECTIVE COAT	SQ YD	11,802	11,802														
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	560	560														
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	576	576														
42400800	DETECTABLE WARNINGS	SQ FT	33	33														
44000100	PAVEMENT REMOVAL	SQ YD	17,044	17,044														
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,330	1,330														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,080	1,080														
44000600	SIDEWALK REMOVAL	SQ FT	2,270	2,270														
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	4	4														
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	463	463														
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	128	128														
44213200	SAW CUTS	FOOT	3,051	3,051														
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	6,705	6,705														
45200300	JOINT OR CRACK FILLING	POUND	1,831	1,831														
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	624	624														
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	527	527														

* DENOTES SPECIALTY ITEMS

FILE NAME =	USER NAME = \$USER#	DESIGNED - JB	REVISED -
\$FILEL#		DRAWN - JB	REVISED -
	PLOT SCALE = \$SCALE#	CHECKED - ACL	REVISED -
	PLOT DATE = \$DATE#	DATE - 10/09/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

SUMMARY OF QUANTITIES 1

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9153	82-1K	ST. CLAIR	107	4
CONTRACT NO. 76C40				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				

Rev.

C:\IC-WORKSPACE\BONDHILL\01-CIVIL\CAD\99 ALL CONTRACTS\CONNS\SHEETS CONTRACT 83\DECONN-83-SHT-SUMMARY1.DGN
 \..DECONN-83-BORDERLIGN.._DECONN-83-SOULIGN.._DECONN-99-HOTIFLIGN.._DECONN-83-LEGENLIGN
 18-26-2009 16:39:59 BONDHILL C:\IC-WORKSPACE\BONDHILL\01-FS-0044\0-TRANS.07\2202\20668-001

