SUMMARY OF QUANTITIES

ST. CLAIR COUNTY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN ROADWAY 100% STATE	CONSTRUCTION TYPE CODE
					J000-2A
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	1,047	1,047	
54213443	END SECTIONS 8"	EACH	2	2	
542C0213	PIPE CULVERTS, CLASS C, TYPE 1 8"	FOOT	14	14	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	54	54	
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	643	643	
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	19	19	
55100200	STORM SEWER REMOVAL 6"	FOOT	1,340	1,340	
55100300	STORM SEWER REMOVAL 8"	FOOT	386	386	
55100400	STORM SEWER REMOVAL 10"	FOOT	409	409	
55100500	STORM SEWER REMOVAL 12"	FOOT	692	692	
55100700	STORM SEWER REMOVAL 15"	FOOT	647	647	
55100900	STORM SEWER REMOVAL 18"	FOOT	190	190	
55101200	STORM SEWER REMOVAL 24"	FOOT	95	95	
55101400	STORM SEWER REMOVAL 30"	FOOT	62	62	
60107700	PIPE UNDERDRAINS 6"	FOOT	140	140	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	6	6	
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	10	10	
60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1	
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3	
60228120	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4	
60228130	MANHOLES, SANITARY, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	7	7	
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9	9	
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	3	3	
60600605	CONCRETE CURB, TYPE B	FOOT	457	457	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	141	141	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,326	4,326	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75	
66400305	CHAIN LINK FENCE, 6'	FOOT	176	176	
66410300	CHAIN LINK FENCE REMOVAL	FOOT	2,290	2,290	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	90	90	
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156	

• DENOTES SPECIALTY ITEMS

Rev.

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - JB	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
	PLOT DATE = $DATE$	DATE - 10/09/09	REVISED -

TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

SUMMARY OF QUANTITIES 2

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9153	82-1K	ST. CLAIR	107	5

CONTRACT NO. 76C40

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

\\DBCONN-03-BORDER\LDGN, \\DBCONN-03-SGN\LDGN, \\DBCONN-99-MUTF\LDGN, \\DBCONN-03-LEGEND\LDGN
10-29-2009, 16:40:01 BONDHUJO C:\TC*WORKSPACE*BONDHUJO\VF5-6844.UP TRANS.BY*2202*20869-001\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 03\DBCONN-03-SHT-SUMMARY2.DGN