SUMMARY OF QUANTITIES

ST. CLAIR COUNTY

	CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY 100% STATE	CONSTRUCTION TYPE CODE										
						J000-2A										
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,137	17,137											
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	87	87											
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	920	920											
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	220	220											
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	170	170											
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,988	6,986											
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,025	1,025											
*	72000100	SIGN PANEL - TYPE 1	SQ FT	89	89											
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10											
*	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	6	6											
*	72900100	METAL POST - TYPE A	FOOT	251	251											
•	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	94	94											
•	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	17,137	17,137											
•	78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	87	87											
•	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	510	510											
•	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	220	220											
•	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	170	170											
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14											
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	868	868											
•	X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3											
	X0324733	COMBINED SEWER REMOVAL 30"	FOOT	519	519											
•	X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	750	750											
•	X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	750	750											
	X2010505	CLEARING, SPECIAL	L SUM	1	1											
	X4020700	AGGREGATE SURFACE COURSE, TYPE B 8"	SQ YD	138	138											
	X0326801	COMBINED SEWERS TO BE CLEANED	FOOT	1,529	1,529											
	X0326802	UTILITY STRUCTURE REMOVAL	EACH	9	9											
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	11,940	11,940											
	Z0007609	BUILDING REMOVAL NO. 9	L SUM	1	1											
	Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	1,231	1,231											
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1											
	Z0017202	DOWEL BARS 1 1/2"	EACH	1,370	1,370											
	Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	47	47											
	Z0022800	FENCE REMOVAL	FOOT	1,724	1,724											
•	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2											
	Z0060400	SANITARY SEWER, TYPE 2 30"	FOOT	500	500											

* DENOTES SPECIALTY ITEMS

Rev

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - JFS	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT DATE = $DATE$	DATE - 10/09/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

SUMMARY OF QUANTITIES 3

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9153	82-1K	ST. CLAIR	107	6
		CONTRACT NO. 76C40		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

..\DBCONN-03-BORDER1.DGN ..\DBCONN-03-SD01.DGN ..\DBCONN-99-MOTIF1.DGN ..\DBCONN-03-LEGEND1.DGN
10-28-2009,17:04:23 BONDHLUD C:\TC-WORKSPACE\BONDHLUD\MF-S 6004.D TRANS.DT\2262\28869 801\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 03\DBCONN-03-SHT-SUMMARY3.DGN