

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000-2A	SIGN STRUCTURES Y002-1C	I-70 OVER CANTEEN CREEK 060-0010 EB 060-0011 WB X071-2A	I-70 OVER IL 157 060-0012 EB 060-0013 WB X271-2A	I-70 OVER BELT LINE RD 060-0014 EB 060-0015 WB X241-2A	I-255 RAMP OVER I-70 060-0205 X271-2A	I-255 RAMP OVER I-70 060-0211 X271-2A		
X0326692	MOTORIST AID CALL BOX REMOVAL	EACH	8	8								
20100500	TREE REMOVAL, ACRES	ACRE	4.2	4.2								
20400800	FURNISHED EXCAVATION	CU YD	100	100								
25000200	SEEDING, CLASS 2	ACRE	4.2	4.2								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	383	383								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	383	383								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	383	383								
25000700	AGRICULTURAL GROUND LIMESTONE	TON	8.8	8.8								
25100115	MULCH, METHOD 2	ACRE	4.2	4.2								
28000400	PERIMETER EROSION BARRIER	FOOT	5694	5694								
28100105	STONE RIPRAP, CLASS A3	SQ YD	43				9	15	19			
28200200	FILTER FABRIC	SQ YD	43				9	15	19			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	140	140								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	86.2	86.2								
40600300	AGGREGATE (PRIME COAT)	TON	595.6	595.6								
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	565	565								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3070	3070								
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1638	1638								
40600990	TEMPORARY RAMP	SQ YD	7695	7695								
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	10861	10861								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	15	15								
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	7343	7343								
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	8154	8154								
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	86155	86155								
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2957	2957								
44004250	PAVED SHOULDER REMOVAL	SQ YD	13847	13847								
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	4	4								

FILE NAME =	USER NAME = keplarcl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr:\pwwork\KFWIDOT\KEPLARCL\d0133826\d876e56-sht-plan.dgn	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			TO	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	4	
PLOT DATE = 10/14/2009	DATE -	REVISED -				SCALE: _____ SHEET NO. OF SHEETS _____ STA. _____ TO STA. _____		CONTRACT NO. 76C56			
						FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT _____					