SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY I000-2A	SIGN STRUCTURES Y002-1C	I-70 OVER CANTEEN CREEK 060-0010 EB 060-0011 WB X071-2A	I-70 OVER IL 157 060-0012 EB 060-0013 WB X271-2A	I-70 OVER BELT LINE RD 060-0014 EB 060-0015 WB X241-2A	I-255 RAMP OVER I-70 060-0205 X271-2A	I-255 RAMP OVER I-70 060-0211 X271-2A		
52100520	ANCHOR BOLTS, 1"	EACH	76				64		12			
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24							24		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	128			40	64	24				
58700300	CONCRETE SEALER	SQ FT	139430			38048	35245	25215	13687	27235		
59000200	EPOXY CRACK INJECTION	FOOT	266						97	169		
59200101	BRIDGE WASHING NO. 1	EACH	2			2						
59200102	BRIDGE WASHING NO. 2	EACH	2				2					
59200103	BRIDGE WASHING NO. 3	EACH	2					2				
59200104	BRIDGE WASHING NO. 4	EACH	1						1			
59200105	BRIDGE WASHING NO. 5	EACH	1							1		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	8						8			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	76	76								
60100074	SHOULDER REMOVAL AND REPLACEMENT 8"	FOOT	87162	87162								
60107600	PIPE UNDERDRAINS 4"	FOOT	85807	85807								
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	2066	2066								
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1								
60260100	INLETS TO BE ADJUSTED	EACH	3	3								
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	14027.5	14027.5								
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	29	29								
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	5	5								
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	12								
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	28	28								
63200310	GUARDRAIL REMOVAL	FOOT	16278	16278								
63500105	DELINEATORS	EACH	368	368								
63500120	DELINEATOR REMOVAL	EACH	368	368								
64200105	SHOULDER RUMBLE STRIP	FOOT	85844	85844								
66500105	WOVEN WIRE FENCE, 4'	FOOT	1200	1200								
66500305	WOVEN WIRE GATES, 4' X 4' SINGLE	EACH	1	1								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18								
67100100	MOBILIZATION	L SUM	1	1								

*Specialty Items

FILE NAME = c:\pw_work\PWIDOT\KEPLARCL\d0133026\d376c56-sht-plan.dgn	USER NAME = keplarcl	DESIGNED - ___	REVISED - ___
		DRAWN - ___	REVISED - ___
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - ___	REVISED - ___
	PLOT DATE = 10/14/2009	DATE - _____	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ | SHEET NO. OF SHEETS | STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	6
		CONTRACT NO. 76C56		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		