

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A	SIGN STRUCTURES Y002-1C	I-70 OVER CANTEEN CREEK 060-0010 EB 060-0011 WB X071-2A	I-70 OVER IL 157 060-0012 EB 060-0013 WB X271-2A	I-70 OVER BELT LINE RD 060-0014 EB 060-0015 WB X241-2A	I-255 RAMP OVER I-70 060-0205 X271-2A	I-255 RAMP OVER I-70 060-0211 X271-2A		
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4' -6" X 5' -3")	FOOT	60		60							
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5' -6")	FOOT	30		30							
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	67.4		67.4							
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	4	4								
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	8	8								
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	152	152								
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10903	10903								
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	84726	84726								
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	8561	8561								
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1990	1990								
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	16430	16430								
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1848	1848								
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	76	76								
78200410	GUARDRAIL MARKERS, TYPE A	EACH	211	211								
78200520	BARRIER WALL MARKERS, TYPE B	EACH	48	48								
78200530	BARRIER WALL MARKERS, TYPE C	EACH	48	48								
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	28	28								
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1878	1878								
80300100	LOCATING UNDERGROUND CABLE	FOOT	104210	104210								
81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	140	140								
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	24	24								
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	54	54								
81400200	HEAVY-DUTY HANDHOLE	EACH	2	2								
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	140	140								
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	8	8								

*Specialty Items

FILE NAME =	USER NAME = keplar01	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr\pwwork\PIWIDOT\KEPLARCL\d0133026\d8	6c56-shr-plan.dgn	DRAWN - ---	REVISED - ---		70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	8			
PLOT SCALE = 50,0000' / IN.	CHECKED - ---	REVISED - ---	REVISED - ---		SCALE: _____ SHEET NO. OF SHEETS _____ STA. _____ TO STA. _____			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
PLOT DATE = 10/14/2009	DATE - -----	REVISED - ---	REVISED - ---					CONTRACT NO. 76C56				