

SUMMARY OF QUANTITIES

| SUMMARY OF QUANTITIES | | | URBAN 100% FED. | CONSTRUCTION TYPE CODE | | | | | | | | | |
|-----------------------|---|-------|---------------------|------------------------|-------------------------------|--|--|--|--|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | ROADWAY 1000-2A | SIGN STRUCTURES Y002-1C | I-70 OVER CANTEN CREEK 060-0010 EB 060-0011 WB X071-2A | I-70 OVER IL 157 060-0012 EB 060-0013 WB X271-2A | I-70 OVER BELT LINE RD 060-0014 EB 060-0015 WB X241-2A | I-255 RAMP OVER I-70 060-0205 X271-2A | I-255 RAMP OVER I-70 060-0211 X271-2A | | | |
| * 87900200 | DRILL EXISTING HANDHOLE | EACH | 7 | 7 | | | | | | | | | |
| * 88600100 | DETECTOR LOOP, TYPE I | FOOT | 438 | 438 | | | | | | | | | |
| * X0323014 | ELECTRIC CABLE IN CONDUIT, CONOGA - 30003 | FOOT | 1272 | 1272 | | | | | | | | | |
| X0323015 | PIEZO ELECTRIC AXLE SENSOR, CLASS II | FOOT | 69 | 69 | | | | | | | | | |
| X0324952 | DETOUR SIGNING | L SUM | 1 | 1 | | | | | | | | | |
| X0325303 | STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES) | SQ FT | 15 | | | | | | 15 | | | | |
| X0325305 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 17 | | | | | | 17 | | | | |
| * X0325702 | NIGHTTIME WORK ZONE LIGHTING | L SUM | 1 | 1 | | | | | | | | | |
| X4066580 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80 | TON | 20534 | 20534 | | | | | | | | | |
| * X5011100 | FOUNDATION REMOVAL | EACH | 3 | 3 | | | | | | | | | |
| * X7330105 | OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A | FOOT | 169 | | 169 | | | | | | | | |
| Z0012500 | CONCRETE CURB REPAIR | FOOT | 14 | | | | | | 14 | | | | |
| Z0017202 | DOWEL BARS 1 1/2" | EACH | 624 | 624 | | | | | | | | | |
| Z0020800 | EROSION CONTROL CURB | FOOT | 747 | 747 | | | | | | | | | |
| Z0020805 | EROSION CONTROL CURB REMOVAL | FOOT | 747 | 747 | | | | | | | | | |
| Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 4 | 4 | | | | | | | | | |
| Z0030150 | IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 4 | 4 | | | | | | | | | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 8 | 8 | | | | | | | | | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 8 | 8 | | | | | | | | | |
| Z0075310 | TIE BARS 3/4" | EACH | 18 | 18 | | | | | | | | | |
| 50800105 | REINFORCEMENT BARS | POUND | 234 | 234 | | | | | | | | | |
| 72700100 | STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | POUND | 748.5 | 748.5 | | | | | | | | | |
| * 73400100 | CONCRETE FOUNDATIONS | CU YD | 2.1 | 2.1 | | | | | | | | | |
| © Z0074600 | TRAINEES | HOUR | 2,000 | 2,000 | | | | | | | | | |
| © Y080 | | | | | | | | | | | | | |

* Specialty Items

| | | | | | | | | | | | |
|---|-----------------------------|------------|-----------|---|---|--|---|--------------------------|---------|-----------------|--------------|
| FILE NAME = | USER NAME = conoverpj | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ct\pw\work\PWIDOT\CONOVERPJ\d0133026\d076c56-sht-plan.dgn | | DRAWN - | REVISED - | | | | 70 | 60-(5,6,7)RS, 60-(6,7)BR | MADISON | 185 | 9 |
| | PLOT SCALE = 50,0000' / IN. | CHECKED - | REVISED - | | | | CONTRACT NO. 76C56 | | | | |
| | PLOT DATE = 10/16/2009 | DATE - | REVISED - | | SCALE: _____ SHEET NO. OF SHEETS _____ STA. _____ TO STA. _____ | | FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT | | | | |