

**PAVING SCHEDULE**

LOCATION	DIRECTION	SIDE	TEMPORARY RAMP	AGGREGATE, SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SHOULDERS, 12'	PAVED SHOULDER REMOVAL	PORTLAND CEMENT CONCRETE SHOULDER 12"	PROTECTIVE COAT	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	INCIDENTAL HOT-MIX ASPHALT SURFACING	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELLING BINDER (MACHINE METHOD), N90	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19-G, N90	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	MATERIAL TRANSFER DEVICE	SHOULDER RUMBLE STRIP	EROSION CONTROL CURB	EROSION CONTROL CURB REMOVAL		
			SQ YD	TON	TONS	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TONS	TONS	TONS	TONS	TONS	TONS	TONS	FOOT	FOOT	FOOT	
564+60.00 TO 565+00.00	EB		196							89																	
Black Lane																											
7+00.00 TO 14+65.00	RAMP 1																0.5	4.9	135		270	405					
7+00.00 TO 14+56.00	RAMP 1	RT		30																				755			
7+00.00 TO 14+56.00	RAMP 1	LT		32																				794			
16+00.00 TO 16+40.00	RAMP 2		125							54																	
14+25.00 TO 14+65.00	RAMP 1		125							54	72																
I-255																											
802+16.00 TO 802+56.00	ROADWAY "B"		187							80	107																
811+68.00 TO 816+54.00	ROADWAY "B"	LT					409	409	409																		
811+71.00 TO 817+48.00	ROADWAY "B"	RT					632	632	632																		
821+50.00 TO 824+03.00	ROADWAY "B"	LT					221	221	221																		
821+93.00 TO 827+36.00	ROADWAY "B"	RT					597	597	597																		
736+01.00 TO 736+41.00	ROADWAY "A"		187							80	107																
516+81.00 TO 517+21.00	RAMP 5		134							63	72																
616+85.00 TO 617+25.00	RAMP 6		134							63	72																
224+86.00 TO 225+26.00	RAMP 2		134							63	72																
100+00.00 TO 100+40.00	RAMP 1		134							134																	
134+50.00 TO 139+53.00	RAMP 1	RT					556	556	556																		
134+50.00 TO 139+21.00	RAMP 1	LT					412	412	412																		
142+13.00 TO 145+21.00	RAMP 1	LT					263	263	263																		
142+26.00 TO 147+22.00	RAMP 1	RT					553	553	553																		
IL - 157																											
00+00.00 TO 3+66.00	RAMP 4																0.5	2.2									
00+00.00 TO 10+11.00	RAMP 4											2957											17				
3+66.00 TO 27+93.00	RAMP 4	LT		97													0.4	3.3	17				17			2431	
3+66.00 TO 27+93.00	RAMP 4	RT		96													0.3	2.2								2416	
10+11.00 TO 27+93.00	RAMP 4												3150				2.3	13.0	177		785	962					
27+53.00 TO 27+93.00	RAMP 4		116							45																	
1+46.00 TO 1+86.00	RAMP 1		116							45																	
1+20.00 TO 1+95.00	RAMP 2													256			0.2	0.8									
1+20.00 TO 5+26.00	RAMP 2	LT		17																						427	
1+20.00 TO 5+26.00	RAMP 2	RT		15																						379	
1+75.00 TO 1+95.00	RAMP 2		169							45							0.1	0.8									
1+95.00 TO 5+26.00	RAMP 2												691				0.4	2.1	39							39	
3+06.00 TO 22+55.00	RAMP 3												3502				1.9	10.6	197		393	590					
3+06.00 TO 22+55.00	RAMP 3	LT		80													0.2	1.8								2017	
3+06.00 TO 22+55.00	RAMP 3	RT		77													0.3	2.6								1929	
22+15.00 TO 22+55.00	RAMP 3		116							45																	
	TOTAL		7695	3422	8286	58	13847	13789	13789	3070	1638	2957	7343	8154	86155	15	86.2	595.6	565	10861	20534	31960	85844	747	747		

LAST SAVED = 9/15/2009  
 PEN TABLE = VB.tbl  
 PLOT DRIVER = TR-Micro6204-Te-Flt.plt

FILE NAME =	USER NAME = sdonahue	DESIGNED -	REVISED -
\\08090\work_order_3\oad\plans\0876855-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0023 / / IN.		CHECKED -	REVISED -
PLOT DATE = 9/16/2009 8:51:42 PM		DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**



**SCHEDULES OF QUANTITIES  
 PAVING**

SCALE: NONE

SHEET NO. 3 OF 12 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	15
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 76C56				