

PIPE UNDERDRAIN SYSTEM SCHEDULE

LOCATION	PIPE UNDERDRAIN 4"				PIPE UNDERDRAIN 4" (SPECIAL)				CONCRETE HEADWALL FOR PIPE UNDERDRAIN	SHOULDER REMOVAL AND REPLACEMENT 8"			
	RIGHT	EB MEDIAN	WB MEDIAN	LEFT	RIGHT	EB MEDIAN	WB MEDIAN	LEFT		RIGHT	EB MEDIAN	WB MEDIAN	LEFT
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		EACH	FOOT	FOOT	FOOT
I-55/70													
378+94 TO 384+12				518								518	
379+96 TO 384+12			416								416		
380+78 TO 384+12		334								334			
381+79 TO 384+12	234									234			
384+12 TO 390+14	602	602	602	610						602	602	602	610
389+45 TO 390+14				140									140
390+14 TO 393+90	382				4	18	18	4	1	4	10	10	4
390+14 TO 397+13		700	700	700						700	700	700	
393+25 TO 397+13	458									458			
397+13 TO 404+16	704	704	704	704	20	18	18	4	1	10	10	10	4
404+16 TO 411+95		780	780		4	18	18	44	1	4	10	10	10
404+16 TO 412+00	784			784						784			784
411+95 TO 418+35		640	640			18	18				10	10	
412+00 TO 418+35				636	6					6			636
412+00 TO 419+00	700									700			
418+35 TO 426+00		766	766	766		18	18	4			10	10	4
419+00 TO 423+30	430				16				1	10			
422+00 TO 429+00	700				2				1	2			
426+00 TO 430+00		400	400	400		18	2	4			10	2	4
429+00 TO 435+00	600				24				1	10			400
430+00 TO 432+67				268						600	400	400	400
430+00 TO 435+00		500	500								500	500	
430+87 TO 435+00				414									414
435+00 TO 440+00		500	500	500	4	18	18	4		4	10	10	4
435+00 TO 445+00	1000									1000			
440+00 TO 445+00		500	500			18	18	2			10	10	2
440+00 TO 450+02				1002							500	500	1002
445+00 TO 450+02	502	502	502		2	2	18			2	2	10	
449+20 TO 450+02	84									84			
450+02 TO 456+00	598				2	18	18	2	1	2	10	10	2
450+02 TO 458+00		798	798	798						598	798	798	798
456+00 TO 466+00	1000				28				1	10			
457+00 TO 458+00				102						1000			
458+00 TO 459+00				100		18	2	4			10	2	4
458+00 TO 464+00		600	600	600							600	600	600
464+00 TO 470+02		602	602	602		18	2	2			10	2	2
466+00 TO 470+02	402				16					10			602
470+02 TO 474+00	398	398	398		12	18	18	2		10	10	10	2
470+02 TO 478+02				800						398	398	398	
473+33 TO 474+00	88									88			800
474+00 TO 477+00	300				8	4	18			8	4	10	
474+00 TO 482+00	800	800	800							300			
478+02					2				1	800	800	800	2

PIPE UNDERDRAIN SYSTEM SCHEDULE

LOCATION	PIPE UNDERDRAIN 4"				PIPE UNDERDRAIN 4" (SPECIAL)				CONCRETE HEADWALL FOR PIPE UNDERDRAIN	SHOULDER REMOVAL AND REPLACEMENT 8"			
	RIGHT	EB MEDIAN	WB MEDIAN	LEFT	RIGHT	EB MEDIAN	WB MEDIAN	LEFT		RIGHT	EB MEDIAN	WB MEDIAN	LEFT
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		EACH	FOOT	FOOT	FOOT
478+02 TO 482+00				398									398
482+00 TO 486+51				452									452
482+00 TO 486+84			484									484	
482+00 TO 487+16		516									516		
482+00 TO 487+49	550										550		
486+51 TO 490+42				392									392
486+84 TO 490+85			402								2		2
487+16 TO 490+85										2			402
487+16 TO 491+24		370									2		370
487+49 TO 491+24	376									2			376
490+42 TO 495+00				458									458
490+85 TO 495+00		416	416							18	18		10
491+24 TO 496+00	476									2			416
495+00 TO 498+00				300							16	16	14
495+00 TO 499+48		448	448										3
496+00 TO 499+85	386									26			10
498+00 TO 502+00				676									386
499+48 TO 504+00		452	452								18	18	10
499+85 TO 503+00	316									2			452
502+00 TO 506+00				400									2
503+00 TO 507+05	514												1
504+00 TO 509+00		500	500								16	16	514
506+00 TO 510+45				446						20		20	10
506+00 TO 510+60	504												2
509+00 TO 510+88		188									16	16	10
509+00 TO 511+43			244										504
509+25 TO 512+50				340									188
514+84 TO 516+64					14								244
516+64 TO 520+40		376	376								12	12	10
516+76 TO 520+48				372									376
519+24 TO 523+60	436									17			10
520+42 TO 520+44											12	12	1
520+44 TO 524+20		376											10
520+44 TO 524+20			376										376
520+52 TO 524+24				372									376
523+64 TO 528+00	436									17			1
524+24 TO 528+00		376	376								12	12	10
524+28 TO 528+00				372									376
528+00 TO 531+83	383												1
528+00 TO 531+89		389											10
528+00 TO 532+64				464									372
528+00 TO 531+94			394										464
531+83					17								394

LAST SAVED = 9/15/2009
 PEN TABLE = VB.tbl
 PLOT DRIVER = TR-MicroPlot-TopFile.plt

FILE NAME =	USER NAME = sdonahue	DESIGNED -	REVISED -
1:\08090\work_order_3\cad\plans\0876656-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0023 / / IN.		CHECKED -	REVISED -
PLOT DATE = 9/16/2009 8:51:44 PM		DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**



**SCHEDULES OF QUANTITIES
 PIPE UNDERDRAINS**

SCALE: NONE SHEET NO. 6 OF 12 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	18
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76C56	