

**PAVEMENT MARKING SCHEDULE**

LOCATION	DIRECTION	SIDE	THERMOPLASTIC PAVEMENT MARKING					PREFORMED PLASTIC PAVEMENT MARKING, TYPE B		RAISED REFLECTIVE PAVEMENT MARKER			SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING			DELINEATORS	DELINEATOR REMOVAL	
			LINE 4" YELLOW	LINE 4" WHITE	LINE 6" YELLOW	LINE 6" WHITE	LINE 8" WHITE	LETTERS AND SYMBOLS WHITE	INLAID - LINE 6" WHITE	LINE 6" WHITE	MARKER REMOVAL	MARKER		MARKER (BRIDGE)	LINE 4"	LINE 6"			LINE 8"
			FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	EACH	EACH		EACH	FOOT	FOOT			FOOT
543+40.00 TO 545+98.00	EB											24	60						
543+52.63 TO 546+10.88	EB	RT										12	259				5	5	
545+06.00 TO 565+00.00	WB	LT																	
545+16.51 TO 565+00.00	WB	LT										240				5952			
545+29.00 TO 565+00.00	WB								490		50	392				980			
545+42.25 TO 565+00.00	WB	RT										240				5874			
545+85.14 TO 565+00.00	EB	LT										240				5745			
545+98.00 TO 565+00.00	EB								480		48	384				960			
546+10.88 TO 565+00.00	EB	RT										228				5670			
546+22.00 TO 565+00.00	EB	RT															5	5	
546+22.00									2										
546+60.00									2										
553+29.00									2										
557+26.00									2										
558+53.00									2										
562+34.00									2										
BLACK LANE																			
391+33.00 TO 393+12.00	RAMP 1	GORE										18	18						
0+00	RAMP 1								2										
5+00.00	RAMP 1								2										
6+00.00	RAMP 1								2										
6+26.00 TO 9+28.00	RAMP 1	LT															4	4	
6+26.00 TO 12+35.00	RAMP 1	RT															8	8	
6+55.10 TO 14+65.21	RAMP 1	LT	834									36	1668						
6+55.10 TO 14+65.21	RAMP 1	RT		811								36	1622						
10+00.00	RAMP 1								2										
11+00.00	RAMP 1								2										
I-255																			
411+01.00 TO 424+56.00	ROADWAY "B"									340		34	34						
417+00.00 TO 424+18.00	ROADWAY "B"	GORE										72	72						
802+56.06 TO 822+60.20	ROADWAY "B"													200		500			
811+70.80 TO 827+36.39	ROADWAY "B"	RT					1566							63		1566			
811+76.46 TO 824+03.26	ROADWAY "B"	LT				1227								50		1227			
421+88.00 TO 433+64.00	ROADWAY "A"									290		30	30						
112+00.00 TO 142+72.43	RAMP 1												770	307		768			
134+49.77 TO 147+21.76	RAMP 1	RT												50		1272			
134+49.77 TO 145+22.17	RAMP 1	LT				1073								43		1072			
477+90.00 TO 481+65.00	RAMP 6	GORE										38	38						
IL - 157																			
493+04.00	RAMP 4								2										
3+34.00	RAMP 4								2										
3+66.00 TO 13+95.00	RAMP 4	LT															14	14	
3+66.00 TO 11+01.00	RAMP 4	RT															10	10	
4+15.37 TO 27+93.14	RAMP 4	LT	2378											288	7134				
4+15.37 TO 27+93.14	RAMP 4	RT		2368										288	7104				
4+50.00	RAMP 4								2										
8+28.00	RAMP 4								2										
9+27.00	RAMP 4								2										
13+22.00	RAMP 4								2										
13+25.00 TO 27+93.00	RAMP 4	RT															23	23	
14+04.00	RAMP 4								2										
18+16.00	RAMP 4								2										
18+81.00	RAMP 4								2										
23+10.00	RAMP 4								2										
23+58.00	RAMP 4								2										
499+86.00 TO 503+12.00	RAMP 1	GORE										32	32						
1+19.99 TO 4+44.04	RAMP 2	LT	337									48	1011						
1+19.99 TO 4+44.04	RAMP 2	RT		325								48	975						
1+20.00 TO 5+26.00	RAMP 2	LT															14	14	
1+20.00 TO 5+26.00	RAMP 2	RT															14	14	
1+98.00	RAMP 2								4										
4+52.00	RAMP 2								2										
510+33.00 TO 512+70.00	RAMP 3	GORE										24	24						
3+06.00 TO 5+15.00	RAMP 3	LT															4	4	
3+06.00 TO 22+55.00	RAMP 3	RT															35	35	

LAST SAVED = 9/15/2009  
 PEN TABLE = VB.tbl  
 PLOT DRIVER = TR: Xerox6204-TopFile.plt

FILE NAME =  
 USER NAME = sdonahue  
 DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE = 9/16/2009 8:51:45 PM

DESIGNED -  
 REVISIONS -  
 REVISIONS -  
 REVISIONS -  
 REVISIONS -

DESIGNED -  
 REVISIONS -  
 REVISIONS -  
 REVISIONS -  
 REVISIONS -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**HORNER &  
 SHIFRIN, INC.**  
 ENGINEERS

**SCHEDULES OF QUANTITIES  
 PAVEMENT MARKING**

SCALE: NONE SHEET NO. 10 OF 12 SHEETS STA. TO STA.

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(5,6,7)RS, 60-(6,7)BR	MADISON	185	22
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 76C56				