January 8, 2010

SUBJECT: Various Routes

Section Various Dist 8 2010-1 Madison, Jersey & Greene Counties

Contract No. 76D13

Item No. 235, January 15, 2010 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Added page 155A to the Special Provisions to include a page that was omitted.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief Bureau of Design and Environment

By: Ted B. Walschleger, P. E.

Tette Salucklyon R.E.

Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; Estimates

TBW:DB:jc

SECTION 1 1.2 Survey Summary & Results

ACM SURVEY RESULTS - Parcel No. 8414005 Single-family Residence RR 1, Box 119 White Hall, Illinois

The following homogeneous building material types were sampled as part of this survey and their results are summarized in the table below:

MTL#	MATERIAL DESCRIPTION	LOCATION	F/NF ¹	COND.2	% ACM ³	# SAMPLES	QUANTITY (ENG/MET)
1	Asphalt roofing/ backing	House roof	NF	Good	ND roofing ND backing	3	2,000 st
2	Black flashing	House roof (around penetrations)	NF	Good	5%	3	20 l: 6.1 lm
3	Felt underlayment	House siding (under wood shingles)	NF	Good	ND	3	1,210 s 112.4 sm
4	Window caulking	House, exterior windows	NF	Good	ND	3	300 l 91.4 lm
5	Window caulking	House, basement windows	NF	Good	4%	3	60 II 18.3 Im
6	Rolled asphalt roofing/ backing	Block building; west roof (under metal cover)	NF	Good	3% roofing ND backing	3	2,080 st 193.2 sm
7	Black sealant	Block building; west roof penetrations	NF	Good	7%	3	1,200 lf 365.8 lm
8	Duct seal tape	Basement, crawlspace	F	Good	40%	3	30 II 9.1 lm
9	Drywall/ joint compound	Original house	F	Good	ND drywall ND joint comp.	3	2,500 st 232.3 sm
10	Drywall	House; family room, basement stairway	F	Good	ND	3	580 st 53.9 sm
11	2' x 4' white fay-in ceiling tile	Family room	F	Good	ND	3	390 st 36.2 sm
12	Felt underlayment	House (under hardwood)	NF	Good	ND	3	1,046 sf 96.6 sm
13	12" x 12" white splined ceiling tile	Balhroom	F	Good	ND	3	80 sf 7.4 sm
14	Multilayer flooring material	Bathroom	NF	Good	ND layer 1 ND layer 2 ND layer 3	3	80 sf 7.4 sm
15	9" x 9" blue w/ white streaks vinyl floor tile/ black mastic	Bathroom (under subfloor)	NF	Good	ND tile 5% mastic	3	40 sf 3.7 sm
16	9" x 9" white w/ pink & blue streaks vinyl floor tile/ black mastic	Bathroom (under subfloor)	NF	Good	ND tile 5% mastic	3	40 sf 3.7 sm
17	Textured ceiling	Family room	NF	Good	3%	3	391 sf 36.3 sm
18	Textured ceiling	Original house	NF	Good	ND	3	1,050 sf 97.5 sm
19	Drywall	Metal clad building	F	Fair	ND	3	2,500 sf 232.3 sm

Illinois Department of Transportation Work Order No. 312

PSI Project No. 0047162 Page 4