

SAN. MANHOLES TO BE RECONSTRUCTED

Table with 2 columns: Description and Quantity. Includes STA. 107+54.3 / 21'RT. (1 EA.) and STA. 109+46.7 / 21.4'RT. (1 EA.).

INLETS TO BE ADJUSTED

Table with 2 columns: Description and Quantity. Includes STA. 110+70.5 / 43.5'RT. (1 EA.) and STA. 110+94.4 / 43.4'RT. (2 EA.).

VALVE BOX TO BE REMOVED

Table with 2 columns: Description and Quantity. Includes STA. 114+47 / 11.26'RT. (4") (1 EA.) and STA. 105+31 / 22.3'RT. (6") (1 EA.).

REMOVE MANHOLE (STORM)

Table with 2 columns: Description and Quantity. Includes STA. 116+83.5 / 24.6'RT. (1 EA.).

REMOVE MANHOLE (SANITARY)

Table with 2 columns: Description and Quantity. Includes STA. 110+29.7 / 20'RT. (1 EA.).

REMOVE INLET (SINGLE)

Table with 2 columns: Description and Quantity. Includes STA. 106+05.5 / LT. & RT. (2 EA.) and STA. 109+73 / LT. & RT. (2 EA.).

MOBILIZATION ENTIRE PROJECT

Table with 2 columns: Description and Quantity. Includes ENTIRE PROJECT (1 L.SUM.).

TRAFFIC CONTROL COMPLETE ENTIRE PROJECT

Table with 2 columns: Description and Quantity. Includes ENTIRE PROJECT (1 L. SUM.).

PAINT PAVEMENT MARKINGS LETTERS AND SYMBOLS

LEFT TURN ARROW

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for left turn arrows, such as STA. 102+13 (8.8 S.F.).

THROUGH ARROW

Table with 2 columns: Description and Quantity. Includes STA. 102+68 "ONLY" (7.0 S.F.) and STA. 102+50 (12.2 S.F.).

PAINT PAVEMENT MARKING LINE, 4"

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for 4" paint marking lines, such as STA. 100+90 TO 102+76 / LT. DOUBLE YELLOW (373 FOOT).

Table with 2 columns: Description and Quantity. Includes STA. 111+22 TO 118+57 / 6'LT SOLID YELLOW (735 FOOT) and STA. 111+22 TO 118+57 / 6'RT SOLID YELLOW (735 FOOT).

PAINT PAVEMENT MARKING LINE, 6"

Table with 2 columns: Description and Quantity. Includes STA. 102+05.7 TO 102+76 (70 FOOT).

RAISED REFLECTIVE PAVEMENT MARKER ENTIRE PROJECT

Table with 2 columns: Description and Quantity. Includes ENTIRE PROJECT (75 EA.).

P.C.C. PAVEMENT, 9" SPECIAL WITH INTEGRAL CURB

Table with 2 columns: Description and Quantity. Includes STA. 104+20 TO 118+57 / LT & RT. (6814 S.Y.).

SHRUB, DIERVILLA LONICERA (BUSH HONEYSUCKLE), 3' HGT CONT.

Table with 2 columns: Description and Quantity. Includes STA. 106+85 TO 107+50 / 32'RT. (17 EA.).

SEEDING SPECIAL ENTIRE PROJECT

Table with 2 columns: Description and Quantity. Includes ENTIRE PROJECT (2952 S.Y.).

CURB STOP AND BOX, 1"

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for curb stop and boxes, such as STA. 106+80 (3426 7TH STR.) (1 EA.).

MAILBOX REMOVAL AND RELOCATION

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for mailbox removal and relocation, such as STA. 105+14.4 / 22.2' RT. (1 EA.).

TEMPORARY EROSION CONTROL COMPLETE ENTIRE PROJECT

Table with 2 columns: Description and Quantity. Includes ENTIRE PROJECT (1 L.SUM.).

CATCH BASIN DOUBLE

Table with 2 columns: Description and Quantity. Includes STA. 106+19 / LT & RT (2 EA.) and STA. 115+23 / LT & RT (2 EA.).

CATCH BASIN SINGLE

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for catch basins, such as STA. 118+00 / RT. (1 EA.).

DUCTILE IRON WATER MAIN FITTINGS 45 BENDS 12"

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for 12" fittings, such as STA. 118+39 / 7'RT. (1 EA.).

Table with 2 columns: Description and Quantity. Includes DUCTILE IRON WATER MAIN FITTING 12 x 10 TEE (1 EA.) and STA. 110+86 / 7'RT. (1 EA.).

DUCTILE IRON WATER MAIN FITTINGS 45 BENDS 8"

Table with 2 columns: Description and Quantity. Includes STA. 107+91.8 / 38'LT. (1 EA.) and STA. 107+95.8 / 34.6'LT. (1 EA.).

DUCTILE IRON WATER MAIN FITTINGS 45 BENDS 4"

Table with 2 columns: Description and Quantity. Includes STA. 114+47 / 29.5'LT. (1 EA.) and STA. 114+52 / 24'LT. (1 EA.).

WATER SERVICE CONNECTION, (CORP) 1"

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for water service connections, such as STA. 106+80 (3426 7TH STR.) (1 EA.).

GATE VALVE AND BOX, 8"

Table with 2 columns: Description and Quantity. Includes STA. 107+96 / 31'LT. (1 EA.).

VINYL FENCE, 6'

Table with 2 columns: Description and Quantity. Includes STA. 105+77 / 38.3' LT TO 107+17.5 LT. (140 FOOT).

GATE VALVE WITH BOX, 4"

Table with 2 columns: Description and Quantity. Includes STA. 114+52.3 / 21.7'LT. (1 EA.).

BUTTERFLY VALVE 10" DIA. W/ VAULT

Table with 2 columns: Description and Quantity. Includes STA. 110+86 / 25.6'RT. (1 EA.).

BUTTERFLY VALVE 12" DIA. W/ VAULT

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for butterfly valves, such as STA. 104+38 / 7'RT. (1 EA.).

STORM SEWER TO BE FILLED

Table with 2 columns: Description and Quantity. Includes STA. 109+32/ 218'LT TO 109+70 / 30'LT. (192 FOOT).

SEGMENTAL CONCRETE BLOCK WALL

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for segmental concrete block walls, such as STA. 106+84 TO 107+63 / RT. (265 S.F.).

RETAINING WALL REMOVAL

Table with 2 columns: Description and Quantity. Includes STA. 105+93 / 31'LT TO 106+58 / 33'LT. (480 S.F.).

Table with 5 columns: F.A.U. RTE, SECTION, COUNTY, TOTAL SHEETS, SHEET NO. Includes 5827, 02-00221-00-RP, ROCK ISLAND, 1, 1.

Table with 2 columns: Description and Quantity. Includes DUCTILE IRON WATER MAIN TEE, 12 x 4 (1 EA.) and STA. 114+52 / 7'RT. (1 EA.).

DUCTILE IRON WATER MAIN TEE 12 x 6

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for 12 x 6 tees, such as STA. 104+46 / 7'RT. (1 EA.).

DUCTILE IRON WATER MAIN TEE 12 x 8

Table with 2 columns: Description and Quantity. Includes STA. 107+95.8 / 7'RT. (1 EA.).

DUCTILE IRON WATER MAIN TEE 4"x 2" W/ STAND TEST CORP, 1"

Table with 2 columns: Description and Quantity. Includes STA. 114+52 / 19'LT. (1 EA.).

STANDARD TESTING CONNECTION, 1"

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for standard testing connections, such as STA. 104+42.4 / 32'RT. (1 EA.).

PRECAST MODULAR RETAINING WALL

Table with 2 columns: Description and Quantity. Includes STA. 105+77 / 38.3' LT TO 106+72.7 / 41.6'LT (1380 S.F.).

DUCTILE IRON WATER MAIN FITTINGS 10" 45 DEGREE BENDS

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for 10" fittings, such as STA. 110+86 / 30.5'RT. (1 EA.).

REMOVE EXISTING VALVE & VAULT

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for valve and vault removal, such as STA. 110+43.3 / 12.6'RT. (1 EA.).

STONE SURFACE SPECIAL

Table with 2 columns: Description and Quantity. Includes STA. 105+77 / 38.3' LT TO 106+84 LT (227 S.Y.).

BOX CULVERT REMOVAL

Table with 2 columns: Description and Quantity. Includes STA. 106+05 / 32' LT. (2 FOOT).

STUMP REMOVAL ONLY

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for stump removal, such as STA. 106+84.5 / 27'LT. (36 UNITS).

FIRE HYDRANT ASSEMBLY COMPLETE

Table with 2 columns: Description and Quantity. Lists various stationing and quantities for fire hydrant assemblies, such as STA. 104+36 / 32'RT. (1 EA.).

ENGINEER'S FIELD OFFICE, TYPE A, (SPL)

Table with 2 columns: Description and Quantity. Includes ENTIRE PROJECT (8 CAL. MO.).




Table with 2 columns: Project information including Department of Public Works, address, and project details like '7TH STREET RECONSTRUCTION & WIDENING'.