85502

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: I000

	CODE NO.	ITEM	UNIT	TOTAL QTY.
•	20200100	EARTH EXCAVATION	CU YD	30
	25200100	SODDING	SQ YD	22
	31102500	SUB-BASE GRANULAR MATERIAL, TYPE C 8"	SQ YD	136
	40600100	BITUMINOUS MATERIAL (PRIME COAT)	GALLON	551
•	40600990	TEMPORARY RAMP	SQ YD	103
•	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	120
•	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	30
•	42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	SQ FT	1,225
	42400800	DETECTABLE WARNINGS	SQ FT	72
•	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,101
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	30
	44000500	COMBINATION CONCRETE CURB & GUTTER REMOVAL	FOOT	300
	44000600	SIDEWALK REMOVAL	SQ FT	1,166
•	44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	1,101
	60255500	MANHOLES TO BE ADJUSTED	EACH	5
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	2
•	60604600	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18 (DOWELLED)	FOOT	300
	67100100	MOBILIZATION	L SUM	1
•	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
•	70300100	SHORT TERM PAVEMENT MARKING	FOOT	24
△	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	388
△	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	373
△	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	82

• SPECIAL PROVISION

△ SPECIALTY ITEMS

LEGEND

(FOR PLAN & PROFILE SHEETS)

GAS LINE — GAS
OVERHEAD ELECTRIC — OH
UNDERGROUND ELECTRIC — E
TELEPHONE T — T
STORM SEWER ST — ST
SANITARY SEWER SS — SS
WATER MAIN W — W
FIBER OPTIC — FO
FENCE
ROW
CENTERLINE
SHOULDER
EXISTING CURB & GUTTER
BUILDING

MANHOLE — MH
ELECTRIC BOX — EB
WATER VALVE — WV
FIRE HYDRANT — FHD
CORP STOP
POWER POLE — PP
POWER POLE ANCHOR
STREET LIGHT/LIGHT POLE — LUM
FOUND REBAR
RECORDED DISTANCE — (100.0')
BUSH
TREE, DECIDUOUS
TREE, CONIFEROUS
TELEPHONE PEDESTAL — TPD

	DESIGNED - DJH	REVISED: 11/02/2009
	DRAWN - DJH	REVISED
PLOT SCALE =	CHECKED -	REVISED

Date: Mon, November 02, 2009 - 9:34am Filename: G:\Dept\3\7230 - East DBQ 2nd STREET\LDD\TITLE SHEET.dwg

WHKS & CO. SPRINGFIELD, IL EAST DUBUQUE, IL DESIGN FIRM #184001036

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES / LEGEND

SCALE: N/A | SHEET NO. 1 OF 1 SHEETS | STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5299	09-00034-00-RS	JO DAVIESS	8	3

CONTRACT NO. 85502

FED. ROAD DIST. NO. 2 | ILLINOIS | FED. AID PROJECT