

SUMMARY OF QUANTITIES						PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE							
					1000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080	
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	100	100							
	25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	100	100							
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1140	1140							
	40600300	AGGREGATE (PRIME COAT)	TON	30	30							
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	360	360							
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	200	200							
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1054	1054							
	42400800	DETECTABLE WARNINGS	SQ FT	88	88							
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	11391	11391							
	44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	335	335							
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	49	49							
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	100	100							
	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	202	202							
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	220	220							
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3							
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1							
	60255500	MANHOLES TO BE ADJUSTED	EACH	6	6							
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	4	4							
	67100100	MOBILIZATION	L SUM	1	1							
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1							
	XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	299	299							

\* - INDICATES SPECIALTY ITEMS

**GENERAL NOTES**

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE THICKNESS OF HOT-MIX ASPHALT MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT SURFACE IS PLACED.
- ROBINSON ENGINEERING FIELD OFFICE SHALL BE NOTIFIED TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION. CALL (708) 331-6700.
- WHEN, IN THE CONSTRUCTION OPERATION, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SO THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH DAY BY THE CONTRACTOR AT HIS EXPENSE. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES SHALL BE FREE FROM ALL DIRT AND DEBRIS. THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- BACKFILLING AND RESTORATION OF AREAS ADJACENT TO SIDEWALK REMOVAL AND REPLACEMENT WILL NOT BE PAID FOR SEPARATELY BUT CONSIDERED INCIDENTAL TO THE CONTRACT.

FILE NAME - 09323-QUAN-01 - 001	USER NAME =	DESIGNED - CMK	REVISED -	<p align="center"><b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b></p>	<p align="center">FAU 6288 (5TH STREET), FAU6290 (8TH STREET) AND FAU 6278 (ELM STREET) LOCAL AGENCY PAVEMENT PRESERVATION (LAPP) SUMMARY OF QUANTITIES &amp; GENERAL NOTES</p>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	CHECKED - CMK	REVISED -	09-00059-00-RS			IRROUOIS	4	2		
PLOT SCALE =	DRAWN - RG	REVISED -	CONTRACT NO. 87436							
PLOT DATE = 07-13-09	CHECKED - RG	REVISED -	SCALE: NA			SHEET NO. 2 OF 4 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT ARA 9089(005)		