

REMOVAL SCHEDULE										
LOCATION		HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	SIDEWALK REMOVAL	ISLAND REMOVAL	PIPE CULVERT REMOVAL	REMOVING INLETS	MAILBOX REMOVAL AND RELOCATION
		SQ YD	SQ YD	SQ YD	FOOT	SQ FT	SQ FT	FOOT	EACH	EACH
BEGIN STATION	END STATION									
BEGIN TO JAYAR										
92+40.00	95+46.41		1161	84				44		1
JAYAR INTERSECTION										
95+46.41	96+11.04	61	463		100					
JAYAR TO NORTHMOOR CT										
96+11.04	98+70.65		845	243				85		4
NORTHMOOR CT. INTERSECTION										
98+70.65	98+22.78	42	277					51		11
NORTHMOOR CT. TO RAILROAD										
98+22.78	105+29.03		2078	442	49	133		221		
RAILROAD TO END										
105+38.26	107+47.11		1440	323	282	166	341	121	1	
KNOXVILLE AVENUE										
1906+09.31	1909+75.13		643							
SHERIDAN ROAD										
249+03.81	251+98.09		79							
TOTAL		103	6986	1092	431	299	341	522	1	16

TOPSOIL, SEEDING, & FERTILIZER NUTRIENTS								
LOCATION		TOPSOIL FURNISH AND PLACE, 6"	SODDING	SODDING, SALT TOLLERANT	SUPPLEMENTAL WATERING	NITROGEN FERTILIZER NUTRIENT 90 (LB/ACRE)	PHOSPHOROUS FERTILIZER NUTRIENT 90 (LB/ACRE)	POTASSIUM FERTILIZER NUTRIENT 90 (LB/ACRE)
		SQ YD	SQ YD	SQ YD	UNIT	POUND	POUND	POUND
BEGIN STATION	END STATION							
BEGINNING TO JAYAR								
92+40.00	95+30.20	1273	696	577	3.8	24	24	24
JAYAR INTERSECTION								
95+30.20	96+21.24	288	185	103	0.9	5	5	5
JAYAR TO NORTHMOOR CT								
96+21.24	98+58.23	853	495	358	2.6	16	16	16
NORTHMOOR CT. INTERSECTION								
98+58.23	99+36.19	316	218	98	0.9	6	6	6
NORTHMOOR CT. TO RAILROAD								
99+36.19	105+29.03	2474	1305	1169	7.4	46	46	46
RAILROAD TO END								
105+38.26	107+47.11	537	298	239	1.6	10	10	10
KNOXVILLE AVENUE								
1906+50.00	1909+74.18	133		133	0.4	2	2	2
SHERIDAN ROAD								
246+00.00	251+75.00	944						
TOTAL		6818	3197	2677	18	110	110	110

TEMPORARY EROSION CONTROL SCHEDULE							
LOCATION		TREE TRUNK PROTECTION	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	INLET FILTERS	TEMPORARY DITCH CHECK	TEMPORARY EROSION CONTROL SEEDING POUNDS
		EACH	FOOT	EACH	FOOT	FOOT	
BEGIN STATION	END STATION						
BEGINNING TO JAYAR							
92+40.00	95+30.20	1	290		6		26
JAYAR INTERSECTION							
95+30.20	96+21.24		91		2		7
JAYAR TO NORTHMOOR CT							
96+21.24	98+58.23		232		6		17
NORTHMOOR CT. INTERSECTION							
98+58.23	99+36.19		67		4		8
NORTHMOOR CT. TO RAILROAD							
99+36.19	105+29.03	7	240	1	11	57	51
RAILROAD TO END							
105+38.26	107+47.11			1	2		10
KNOXVILLE AVENUE							
1906+50.00	1909+74.18		393				3
SHERIDAN ROAD							
246+51.53	247+06.99	2				60	19
TOTAL		10	1313	2	31	117	141

EARTHWORK				
LOCATION		EARTH EXCAVATION	ADJUSTED EXCAVATION FOR SHRINKAGE (25%)	EMBANKMENT
		CU YD	CU YD	CU YD
BEGIN STATION	END STATION			
BEGINNING TO JAYAR				
92+40.00	95+30.00	858	644	367
JAYAR INTERSECTION				
95+30.00	96+25.00	441	331	116
JAYAR TO NORTHMOOR CT				
96+25.00	98+50.00	862	647	263
NORTHMOOR CT. INTERSECTION				
98+50.00	99+50.00	409	307	160
NORTHMOOR CT. TO RAILROAD				
99+50.00	105+29.03	2148	1611	900
RAILROAD TO END				
105+38.26	107+47.11	559	419	17
KNOXVILLE AVENUE				
1906+50.00	1909+74.18	89	67	4
SHERIDAN ROAD				
246+00.00	251+75.00	242	182	2
TOTAL		5608	4206	1829
ADJUSTMENT FOR TEMPORARY PAVEMENT		490	360	360
ROUNDED TOTAL		6100	4570	2190

TREE REMOVAL SCHEDULE				
LOCATION			(6-15) UNIT	OVER 15 UNIT
STATION	OFFSET	LT/RT		
BEGINNING TO JAYAR				
92+72.81	29.82	LT		17
92+89.53	33.07	LT		18
JAYAR TO NORTHMOOR CT.				
98+55.86	32.17	LT		39
NORTHMOOR CT. TO RAILROAD				
103+76.75	40.44	LT	14	
103+81.50	41.66	LT	15	
104+00.56	40.43	RT		18
104+27.37	43.55	RT	9	
104+36.84	43.46	RT	9	
104+93.11	45.92	RT		19
SHERIDAN ROAD				
246+95.20	38.94	RT	13	
246+99.30	39.79	RT	10	
247+07.00	41.3	RT		17
TOTAL			70	128



FILE NAME =	USER NAME = Ander80846	DESIGNED - RLA	REVISED -
I:\09Jobs\09\0227B\CADD\Road\Sheet\c-09\sch.dgn		DRAWN - RLA	REVISED -
PLOT SCALE = 5.0000 ' / in.		CHECKED - CAL	REVISED -
PLOT DATE = 11/17/2009		DATE - 10/16/2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6647	08-00302-00-PV	PEORIA	85	5
09-00047-01-PV		CONTRACT NO. 89526		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT ARA-M-5093(139)		