

INDEX OF SHEETS

- 1 COVER
- 2 INDEX OF SHEETS, GENERAL NOTES AND SUMMARY OF QUANTITIES
- 3 TYPICAL SECTIONS
- 4 SCHEDULE OF QUANTITIES
- 5 PATCHING PLAN
- 6 PATCHING, MILLING, AND OVERLAY PLAN
- DISTRICT 4 STANDARDS**
- 7-9 406101-D4 BUTT JOINTS
- 10 440001-D4 HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)
- 11-12 780001-D4 TYPICAL PAVEMENT MARKINGS

HIGHWAY STANDARDS

280001-05	701311-03
	701501-05
442101-07	701701-06
442201-03	701901-01
	780001-02

COMMITMENTS

No Commitments have been made for this Project

JOB SPECIFIC NOTES

Manhole Covers and Water Valve Lids to be adjusted by the CITY OF CHILLICOTHE.

UTILITY COMPANY REPRESENTATIVES

WATER AND SEWER: CITY OF CHILLICOTHE 908 N. SECOND CHILLICOTHE, IL 61523	ELECTRIC AND GAS: AMEREN/CILCO 8420 N. UNIVERSITY PEORIA, IL 61615	TELEPHONE: VERIZON
--	--	------------------------------

GENERAL NOTES

PROPERTY OWNER ACCESS REQUIREMENT

Access must be maintained to all existing properties during construction per Article 107.09 unless arrangements are made in writing by the Contractor with the property owners with a copy to the Engineer for short-term closures.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

Mixture Uses(s):	SURFACE	LEVELING BINDER (HM)
RAP % (Max)**:	10%	25%
AC/PG:	SBR or SBS 76-22	PG 64-22
Design Air Voids:	4.0% @ N = 70	4.2% @ N = 30
Mixture Composition (Gradation Mixture):	IL 9.5 OR IL 12.5	IL 9.5 OR IL 12.5
Friction Aggregate:	MIX "D"	MIX "C"
Mixture Weight:	112#/SQ YD/IN	112#/SQ YD/IN

**If the RAP option is selected, the asphalt cement grade may need to be adjusted; This will be determined by the Engineer.

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				PEORIA COUNTY 100% FEDERAL CONSTRUCTION TYPE CODE
				ROADWAY URBAN
				1000
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(BIT.)
40800115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GAL	990	990
40800300	AGGREGATE (PRIME COAT)	TON	12	12
40800400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	8	8
40800515	LEVELING BINDER (HAND METHOD) N30	TON	8	8
40800885	CONSTRUCTING TEST STRIP	EACH	1	1
40800985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	267	267
40800980	TEMPORARY RAMP	SQ YD	44	44
40803540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,106	1,106
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	343	343
44201284	CLASS B PATCH EXPANSION JOINT	FOOT	160	160
44201286	DEFORMED BARS - EXPANSION JOINT	EACH	32	32
44201349	CLASS C PATCHES TYPE I, 10 INCH	SQ YD	6	6
44213200	SAW CUTS	FOOT	1,842	1,842
67100100	MOBILIZATION	L SUM	1	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	11	11
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	458	458
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	80	80
X0321020	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) VARIABLE DEPTH	SQ YD	2,474	2,474
XX005138	CLASS B PATCHES (SPECIAL)	SQ YD	236	236
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0017202	DOWEL BARS 1 1/2"	EACH	165	165
Z0075310	TIE BARS 3/4"	EACH	47	47

* SPECIALTY ITEMS

FILE NAME = L:\CHIL0001\PLANS-XREFS\ 02-INDEX NOTES S00.DGN	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF CHILLICOTHE - TRUITT AVENUE INDEX OF SHEETS, GENERAL NOTES AND SUMMARY OF QUANTITIES		F.A.U. RTE. 6548	SECTION 09-00008-00-RS	COUNTY PEORIA	TOTAL SHEETS 12	SHEET NO. 2	
	PLOT SCALE =	DRAWN -	REVISED -		SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 89548				
	PLOT DATE = 18-01-09	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							