

**STORM SEWER REMOVAL**

STATION TO STATION	SIDE	STORM SEWER REMOVAL 12" FOOT
<b>MORGAN STREET</b>		
31+93.6	31+95.4	LT 9.1
32+3.2	32+16.4	RT 14.5
32+16.4	32+90.2	RT 73.7
34+35.0	34+43.7	LT 69.6
36+8.3	36+38.9	RT 30.6
36+38.9	36+43.6	RT 5.9
36+63.4	36+66.8	LT 12.9
<b>COURT STREET</b>		
42+17.1	42+81.0	LT 63.9
44+41.1	45+11.4	RT 70.3
45+6.3	45+11.4	RT 55.0
45+11.4	45+67.1	RT 55.7
45+53.3	46+38.6	LT 85.3
45+67.1	45+76.6	RT 20.1
46+38.6	46+53.7	LT 19.0
<b>TOTAL</b>		<b>585.6</b>
<b>USE</b>		<b>586</b>

**ESTIMATED QUANTITIES**

ITEM	UNIT	QUANTITY
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR HANDLING UTILITY CONFLICTS		
ADJUSTING WATER MAIN, 4"	FOOT	200
ADJUSTING WATER MAIN, 6"	FOOT	200
ADJUSTING WATER MAIN, 8"	FOOT	200
ADJUSTING WATER MAIN, 10"	FOOT	200
ADJUSTING SANITARY SEWERS, 8 INCH OR LESS	FOOT	400
ADJUSTING WATER SERVICE LINES	FOOT	200
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR HANDLING EXISTING DRAINAGE TILES OR STORM SEWER		
STORM SEWERS, SPECIAL 4"	FOOT	200
STORM SEWERS, SPECIAL 6"	FOOT	200
STORM SEWERS TO BE CLEANED	FOOT	1,200
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR THE REMOVAL OF EXISTING WATER MAIN ASSOCIATED WITH THE CONSTRUCTION OF THE PROPOSED WATER MAIN/ SERVICES AND STORM SEWER		
WATER MAIN REMOVAL	FOOT	300

**BASEMENT VAULTS**

STATION	SIDE	BUILDING DESCRIPTION	RETAINING WALL SQ FT	TRENCH BACKFILL CU YD
<b>MORGAN STREET</b>				
39+90.0	RT	EDWARD JONES	160	54
<b>SANDY STREET</b>				
54+82.0	LT	FARMERS STATE BANK	80	221
<b>MAUVAISTERRE STREET</b>				
63+87.0	RT	US BANK	80	238
64+55.0	RT	CLIP TO MANIA II	56	7
64+96.0	RT	DR. BECKETT	56	32
65+24.0	RT	ECLECTIC ART GALLERY	152	105
<b>TOTAL</b>			<b>584</b>	<b>657</b>
<b>USE</b>			<b>584</b>	<b>657</b>

**ITEMS TO BE REMOVED OR ADJUSTED**

STATION	OFFSET	FIRE HYDRANTS TO BE ADJUSTED	FIRE HYDRANTS TO BE REMOVED	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED	INLETS TO BE ADJUSTED	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	INLETS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	VALVE VAULTS TO BE REMOVED	FILLING VALVE VAULTS	VALVE BOXES TO BE ADJUSTED	VALVE BOXES TO BE REMOVED	REMOVING MANHOLES	REMOVING INLETS
EACH														
<b>MORGAN STREET</b>														
31+75.6	4.2' LT				1									
32+03.2	6.6' RT				1									
32+10.7	17.5' RT				1									
32+16.4	0.5' RT													1
32+34.0	13.5' LT													
32+42.6	3.2' LT											1		
32+42.9	6.4' LT		1											
32+79.4	19.9' LT													
33+32.7	11.4' LT													
33+49.0	12.1' LT											1		
33+97.6	11.8' LT													
34+23.0	3.8' LT		1											
34+23.8	16.7' LT				1									
34+25.4	4.1' LT											1		
34+35.0	18.8' LT													1
34+43.7	87.5' LT													1
34+61.9	12.8' LT													
34+68.0	1.4' LT											1		
35+10.7	12.1' LT													
35+52.1	81.7' LT											1		
35+71.2	12.1' LT													
36+08.3	6.5' RT													1
36+38.9	5.3' RT													1
36+43.6	1.8' RT													1
36+53.7	19.7' RT				1									
36+63.1	1.7' RT									1				
36+73.0	29.5' RT										1			
37+10.9	0.1' RT								1					
<b>COURT STREET</b>														
41+93.7	22.9' RT						1							
42+42.0	1.1' LT													1
42+58.3	14.8' LT													1
42+80.3	14.9' LT													1
42+81.0	5.4' LT													1
42+81.6	13.2' RT													
43+47.5	18.1' RT											1		
43+51.4	88.8' RT													
43+56.9	12.2' RT													
43+94.4	85.2' RT													
44+2.0	0.2' RT								1					
44+9.9	11.9' RT													
44+25.2	37.5' RT		1											
44+25.3	45.8' RT											1		
44+36.2	7.4' RT				1									
44+41.1	79.3' RT													1
44+62.8	11.4' RT													
44+9.2	11.2' RT													
45+11.4	82.7' RT												1	
45+22.7	79.6' RT											1		
45+53.3	6.8' LT													1
45+79.5	16.8' RT													

CONTINUED ON NEXT SHEET

FILE NAME = v:\2522\plaza plans\25220802.dgn	USER NAME = jwhite	DESIGNED - JRB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>CITY OF JACKSONVILLE DOWNTOWN PLAZA STREETS RECONSTRUCTION SCHEDULES OF QUANTITIES</b>	F.A.U. RTE. N/A	SECTION 05-00121-00-PV	COUNTY MORGAN	TOTAL SHEETS 74	SHEET NO. 11	
PLOT SCALE = 1:8000' / IN.	CHECKED - JRB	REVISIED -	SCALE: N/A			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT			
PLOT DATE = 9/25/2009	DATE - 09/25/09	REVISIED -	CONTRACT NO. 93504								