

WATER MAIN SCHEDULE

STATION	SIDE	TYPE	WATER MAIN			WATER VALVES WITH VALVE BOX		FIRE HYDRANT COMPLETE	LINE STOPS		
			4"	6"	10"	6"	10"		4"	6"	10"
			FEET			EACH		EACH			
MORGAN STREET											
31+85.0	RT	90° BEND WM			265						
31+99.6	RT	LS							1		
31+99.7	RT	WV				1					
31+99.8	RT	LS		10						1	
32+26.6	LT	FH WM		25			1				
34+30.8	RT	WV				1					
34+44.8	RT	WV				1					
34+47.9	RT	TEE WM			121						
34+48.0	RT	LS								1	
34+53.1	RT	WV WM		226		1					
34+70.9	LT	FH WM		25			1				
36+37.2	LT	FH WM		18			1				
36+63.0	RT	LS								1	
36+63.3	RT	WV WM		10		1					
36+63.4	RT	LS								1	
COURT STREET											
41+85.4	LT	LS WM		10						1	
41+94.7	LT	WV				1					
41+94.7	LT	LS WM			24						1
41+94.7	LT	WV				1					
41+94.7	LT	LS								1	
41+94.7	LT	WV WM		482		1					
42+25.3	RT	FH WM		19			1				
44+05.5	RT	FH WM		26			1				
44+23.2	LT	LS								1	
44+23.2	LT	REDUCER WV WM		10		1					
44+23.2	LT	LS								1	
46+28.7	RT	FH WM		18			1				

STATION	SIDE	TYPE	WATER MAIN			WATER VALVES WITH VALVE BOX		FIRE HYDRANT COMPLETE	LINE STOPS		
			4"	6"	10"	6"	10"		4"	6"	10"
			FEET			EACH		EACH			
46+59.7	LT	LS REDUCER								1	
46+59.8	LT	WM WV		10			1				
46+60.0	LT	LS								1	
SANDY STREET											
51+85.0	LT	90° BEND WM			238						
51+88.3	LT	WV					1				
51+95.7	LT	LS WM		10							1
51+95.7	LT	WV					1				
51+95.9	LT	LS									1
53+81.8	RT	FH WM		25				1			
54+19.3	LT	WV					1				
54+22.0	LT	LS WM			28						1
54+22.2	LT	WV					1				
54+22.9	LT	LS									1
54+25.3	LT	WV					1				
54+31.5	LT	LS									1
MAUVAUSTERRE STREET											
61+85.0	RT	90° BEND WM		493							
61+95.5	RT	WV					1				
61+98.5	RT	LS								1	
61+98.7	RT	WV REDUCER WM					1				
61+99.6	RT	LS		44						1	
64+24.1	RT	LS WM			35						1
64+24.2	RT	WV					1				
64+24.3	RT	LS									1
64+27.4	RT	WV					1				
64+71.8	LT	FH WM		25				1			
66+61.7	LT	LS									1
66+61.8	LT	WV WM		10			1				
66+61.9	LT	LS									1
TOTALS			44	1,487	676	13	7	8	6	11	6

NOTE: TRENCH BACKFILL TO BE INCLUDED IN COST OF WATER MAIN CONSTRUCTION

FILE NAME = v:\2522\plaza plans\25220002.dgn	USER NAME = jwhite	DESIGNED - JRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF JACKSONVILLE DOWNTOWN PLAZA STREETS RECONSTRUCTION SCHEDULES OF QUANTITIES	F.A.J. RTE. N/A	SECTION 05-00121-00-PV	COUNTY MORGAN	TOTAL SHEETS 74	SHEET NO. 15		
PLOT SCALE = 1/8" = 1' / IN.	CHECKED - JRB	REVISIED -	SCALE: N/A			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				
PLOT DATE = 9/25/2009	DATE - 09/25/09	REVISIED -	CONTRACT NO. 93504									