

| PLAN | BY | DATE |
|------|----|------|
| NO. | | |

| NO. | FILE NAME |
|-----|-----------|
| | |

| PROFILE | BY | DATE |
|---------|----|------|
| NO. | | |

| NO. | NOTATIONS |
|-----|-----------|
| | |

HRG PROJECT NO. 180756
 HRG PROJ. CONTACT: 180756_SPA_S00.dgn
 PLOT DRIVER: ilacr_dwg.ctb
 PLOT TABLE: plot006.tbl

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE |
|--------------|--|-------|----------------|-----------------------------------|
| | | | | CMAQ 80% FED/20% LOCAL 0021 |
| 20200100 | EARTH EXCAVATION | CU YD | 400 | 400 |
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD | 445 | 445 |
| 20400800 | FURNISHED EXCAVATION | CU YD | 2,740 | 2,740 |
| 20700220 | POROUS GRANULAR EMBANKMENT | CU YD | 350 | 350 |
| 20800150 | TRENCH BACKFILL | CU YD | 115 | 115 |
| 21101505 | TOPSOIL EXCAVATION AND PLACEMENT | CU YD | 811 | 811 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 710.0 | 710.0 |
| + 25200110 | SODDING, SALT TOLERANT | SQ YD | 9,890.0 | 9,890.0 |
| + * 25200200 | SUPPLEMENTAL WATERING | UNIT | 611 | 611 |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 205 | 205 |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 30.0 | 30.0 |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 1,070.0 | 1,070.0 |
| 28000510 | INLET FILTERS | EACH | 11 | 11 |
| * 30300112 | AGGREGATE SUBGRADE IMPROVEMENT 12" | SQ YD | 1,565.0 | 1,565.0 |
| 35101600 | AGGREGATE BASE COURSE, TYPE B 4" | SQ YD | 1,115.0 | 1,115.0 |
| 40600275 | BITUMINOUS MATERIALS (PRIME COAT) | POUND | 1,763 | 1,763 |
| 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 188 | 188 |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 145 | 145 |
| 40604060 | HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50 | TON | 110 | 110 |
| 42400300 | PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH | SQ FT | 7,495.0 | 7,495.0 |
| * 42400800 | DETECTABLE WARNINGS | SQ FT | 75.0 | 75.0 |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 1,245.0 | 1,245.0 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 850.0 | 850.0 |



* SPECIAL PROVISION
 + SPECIALTY ITEM



HRGreen.com
 Illinois Professional Design Firm
 #184-001222

KMI
 Kalsouni Mehd, Inc.
 ARCHITECTS & ENGINEERS
 223 W. Jackson Blvd., Suite 1010 Chicago, IL 60606
 TEL: (312) 980-1500 FAX: (312) 980-0892

| | |
|------------------|-------------------------------|
| DESIGNED - JJS | REVISED - Δ 12/16/2020 |
| DRAWN - WJH | REVISED - |
| CHECKED - JJS | REVISED - |
| DATE - 10/5/2020 | REVISED - |

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

| SUMMARY OF QUANTITIES | | |
|-----------------------|---------------------|--------------|
| SCALE: NTS | SHEET 1 OF 4 SHEETS | STA. TO STA. |
| | | |

| F.A.U. RTE. | SECTION NO. | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|----------------|--------|--------------------|-----------|
| N/A | 12-00097-00-BR | LAKE | 65 | 4 |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 61F89 | |