



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 14, 2020

SUBJECT: Route FAU 2663 (Clarendon Hills Road)  
Section 19-03126-00-RS  
DuPage County  
Contract No. 61G59  
Item 143  
January 15, 2021 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

### **1. Revised page 8 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

**HMA DRIVEWAY REMOVAL & REPLACEMENT (SECTIONS 440)**

This item will comply with the requirements of Sections 440 of the *Standard Specifications* as modified herein:

This item includes the removal and replacement of bituminous driveways. Only those areas as specifically directed by the Engineer will be saw-cut, removed, and replaced. Any other areas damaged by the Contractor will be removed and replaced at the Contractor's cost.

Bituminous driveway pavement designated for replacement will be overlaid with 2" of Hot-Mix Asphalt Surface Course, IL-9.5, Mix "D," N50 and 3" Hot-Mix Asphalt Binder Course, IL-19.0, N50, and will conform to existing shapes. The Contractor will be required to saw-cut the existing bituminous driveways to a minimum depth of 5" at the locations designated by the Engineer. The existing sub-base will be compacted by mechanical means.

Cost of saw cutting will be considered included in the contract unit price bid for this item.

Payment will be made at the contract unit price per square yard (SQ YD) of **DRIVEWAY PAVEMENT REMOVAL & HMA DRIVEWAY PAVEMENT 5"**.