



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 21, 2020

SUBJECT: Various Routes
Section 2020-222-I
Will County
Contract No.62M99
Item No. 176, January 15, 2021 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 12 and 13 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

5. **PARKING:** It will be the Contractor's responsibility to ascertain ALL parking locations for each cleaning cycle. Parking is permitted along various routes at various times within certain municipalities. A listing of parking locations is included in the special provisions beginning on page number 21. Municipalities may add and or eliminate locations throughout the term of this contract. The contractor will be required to provide "No Parking" signs at least 24 hours in advance of sweeping work to prohibit parking as needed during each cleaning period. Temporary no parking signs shall be minimum size of 17" X 22" with lettering not less than one inch in height, setting forth the day or days and hours parking is prohibited. Temporary no parking signs shall be constructed form materials that will resist tearing and weather. Temporary no parking signs shall be placed at a height not less than five (5) feet from the existing ground height to the bottom of the sign and facing the direction of traffic. The temporary no parking signs shall be approved by the Engineer prior to use. The contractor shall solicit no parking enforcement assistance from the municipalities. *The contractor shall submit documentation to the Engineer verifying the solicitation of the no parking enforcement from the municipalities for each cleaning cycle.* The contractor shall remove the temporary "No Parking" signs promptly after completing sweeping operations. Furnishing, installing and removing temporary "No Parking" signs will not be paid for as separate items, but the costs shall be considered as included in the contract unit price for the cleaning cycle involved, and no additional compensation will be allowed.
6. **METHOD OF MEASUREMENT:** The Full Arterial Cleaning Cycle pay item shall be measured for payment in concrete curb miles. The length of concrete curb miles paid for shall include the cleaning of all location limits and areas of debris as described in LOCATION AND LIMITS OF CLEANING and no additional compensation will be allowed.
7. **CLEANING CYCLE ADJUSTMENT BASIS:** The total curb miles for a complete Full Arterial Cleaning Cycle is estimated to be approximately **271.6** concrete curb miles and is the basis to be used in computations when a cleaning cycle cannot be completed due to unforeseen highway operational reasons.

Revised 12/21/20

ARTERIAL HIGHWAYS TO BE CLEANED

JOLIET TEAM SECTION CLEANING LOCATIONS

KEY LOC.	ROUTE	LIMITS	EST. CURB MILES
J1	IL-53	Old Chicago Dr to Ruby St	30.3
J2	US-30 (Plainfield Rd)	IL-59 to Black Rd	17.7
J3	Theodore St	Larkin Ave to IL-53	4.0
J4	IL-7 (Larkin Ave.)	US-6 to US-30	8.6
J5	US-52 (Jefferson St.)	Larkin Ave to Kendall County Line (County Line Rd.) Including: Channahon St. from Dante Ct. to SW Frontage Rd. (I-55 Frontage Rd.)	11.6
J6	IL-171	E.J.&E. Railroad to State St	10.1
J7	US-6	Henderson Ave to Wolf Rd	5.1
J8	IL-7	IL-53 to Wolf Rd	30.6
J9	IL-59	143rd St to I-55	26.7
J10	143rd St	US-30 to IL-59	2.2
J11	IL-126	Kendall County Line to I-55	2.1
J12	Stateville Rd	IL-53 to Prison Loop Dr.	1.2
J13	Joliet Rd	IL-53 to I-55	4.0
J14	New Ave	Lemont Rd/State St to IL-171	1.6
J15	US-6	Grundy County Line to McDonough St.	11.2
Total Joliet Curb Miles			167

Revised 12/21/20