

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	URBAN 20% FED, 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				BITUMINOUS PAVEMENT		PROPOSED IL 53 OVER E. BR. DUPAGE RIVER (SN 022-0181)	LIGHTING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10	1000-2A 10		X031-2A	Y030-1E
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	112	112			
20101000	TEMPORARY FENCE	FOOT	90	90			
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5			
20200100	EARTH EXCAVATION	CU YD	7,962	7,962			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,505	2,505			
20400800	FURNISHED EXCAVATION	CU YD	5,713	5,713			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	63			63	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	823	823			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,556	2,556			
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	16,795	16,795			
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	359	359			
* 25000210	SEEDING, CLASS 2A	ACRE	2.50	2.50			
* 25100630	EROSION CONTROL BLANKET	SQ YD	30,798	30,798			
* 25200200	SUPPLEMENTAL WATERING	UNIT	5	5			
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	340	340			
* 28000720	MULCH, METHOD 2	ACRE	0.5	0.5			
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,194			1,194	
28200200	FILTER FABRIC	SQ YD	1919	636		1,283	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	948	948			
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	106	106			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.3	6.3			
40600300	AGGREGATE (PRIME COAT)	TON	5	5			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	19	19			
40603090	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	133	133			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	118	118			
40701891	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	SQ YD	2,497	2,497			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	390	390			
44000100	PAVEMENT REMOVAL	SQ YD	3,271	3,271			
44000166	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4"	SQ YD	1,053	1,053			

*Specialty Items

S00-1



FILE NAME = P:_2002\022019\004\Cadd\Sheet Files\Part 1	DESIGNED - TAI	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		F.A.P. ROUTE 870 (ILLINOIS 53) OVER EAST BRANCH DUPAGE RIVER	F.A. RTE. 870	SECTION 533 X-B-R-1	COUNTY DUPAGE	TOTAL SHEETS 87	SHEET NO. 3
SUM. QUAN. 1.SHT	DRAWN - AEG	REVISED -			SUMMARY OF QUANTITIES		CONTRACT NO. 60B95			
PLOT SCALE = 1" = 50'	CHECKED - PJM	REVISED -			SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		
PLOT DATE = 10/10/2008	DATE - 10/15/08	REVISED -								