

SUMMARY OF QUANTITIES

CODE	ITEM DESCRIPTION	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				BITUMINOUS PAVEMENT		PROPOSED IL 53 OVER E. BR. DUPAGE RIVER (SN 022-0181)	LIGHTING
44000700	APPROACH SLAB REMOVAL	SQ YD	316	1000-2A 316		X031-2A	Y030-1E
44004250	PAVED SHOULDER REMOVAL	SQ YD	105	105			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,187	1,187			
48203039	HOT-MIX ASPHALT SHOULDERS, 10 1/2"	SQ YD	2,786	2,786			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1	
50200100	STRUCTURE EXCAVATION	CU YD	66			66	
50300225	CONCRETE STRUCTURES	CU YD	224.4			224.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	355.7			355.7	
50300260	BRIDGE DECK GROOVING	SQ YD	611			611	
50300280	CONCRETE ENCASEMENT	CU YD	22.4			22.4	
50300300	PROTECTIVE COAT	SQ YD	717			717	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	91,030			91,030	
50800515	BAR SPLICERS	EACH	258			258	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	3960			3960	
51202305	DRIVING PILES	FOOT	3960			3960	
51203600	TEST PILE STEEL HP12X53	EACH	4			4	
51204650	PILE SHOES	EACH	68			68	
51500100	NAME PLATES	EACH	1			1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	46			46	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	8	8			
60107700	PIPE UNDERDRAINS 6"	FOOT	284	284			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	211			211	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	662.5	662.5			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	412.5	412.5			
63801205	TEMPORARY MODULAR GLARE SCREEN	FOOT	308	308			
66400305	CHAIN LINK FENCE, 6'	FOOT	401	401			

* Specialty Items

S00-2



Rev.

FILE NAME =	DESIGNED - TAI	REVISED -	F.A.P. ROUTE 870 (ILLINOIS 53) OVER EAST BRANCH DUPAGE RIVER	F.A. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PA\2002\020019.004\Cadd\Sheet Files\Part	DRAWN - AEG	REVISED -		870	533 X-B-R-1	DUPAGE	87	4
	CHECKED - PJM	REVISED -	STATE OF ILLINOIS	SUMMARY OF QUANTITIES				
	DATE - 10/15/08	REVISED -	DEPARTMENT OF TRANSPORTATION	SCALE: NONE	SHEET NO.	OF	SHEETS	STA. TO STA.
				FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				CONTRACT NO. 60B95