

PAVEMENT MARKING ITEMS

	THERMOPLASTIC PAVEMENT MARKING - LT & SYM (SQ FT)	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 6" (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 12" (FOOT)	THERMOPLASTIC PAVEMENT MARKING - LINE 24" (FOOT)	PREFORMED PLASTIC PAVEMENT MARKING - LINE 4" (FOOT)	PREFORMED PLASTIC PAVEMENT MARKING - LINE 12" (FOOT)
905+45 907+60		359					
907+60 911+20		1,440		28			
911+20 915+60		2,640		40			
915+60 917+19						954	71
917+19 918+75		936		18			
918+75 920+00		750		30			
920+00 922+13		1,331		54			
922+13 924+10	78	1,182	197		30		
<b>TOTAL</b>	<b>78</b>	<b>8,638</b>	<b>197</b>	<b>170</b>	<b>30</b>	<b>954</b>	<b>71</b>

TEMPORARY SOIL RETENTION SYSTEM

START STATION	END STATION	LENGTH (FOOT)	HEIGHT (FOOT)	AREA (SQ FT)
911+20.0	911+50.0	30.0	0.01	0.4
911+50.0	912+00.0	50.0	0.13	6.7
912+00.0	912+50.0	50.0	0.45	22.5
912+50.0	913+00.0	50.0	0.96	47.8
913+00.0	913+50.0	50.0	1.55	77.5
913+50.0	913+75.0	25.0	1.55	38.8
913+75.0	914+00.0	25.0	1.21	30.2
914+00.0	914+50.0	50.0	1.88	94.0
914+50.0	915+00.0	50.0	2.51	125.5
915+00.0	915+50.0	50.0	3.03	151.7
915+50.0	915+89.5	39.5	3.43	135.5
915+89.5	915+91.5	2.0	4.38	8.8
916+86.5	917+00.0	13.5	3.55	47.9
917+00.0	917+50.0	50.0	3.24	162.0
917+50.0	918+00.0	50.0	2.66	133.0
918+00.0	918+50.0	50.0	2.14	107.0
918+50.0	919+00.0	50.0	1.72	86.2
919+00.0	919+50.0	50.0	1.25	62.5
919+50.0	920+00.0	50.0	1.68	84.0
920+00.0	920+50.0	50.0	1.11	55.5
920+50.0	921+00.0	50.0	0.55	27.3
921+00.0	921+50.0	50.0	0.18	9.0
921+50.0	921+85.0	35.0	0.03	1.1
<b>TOTAL</b>				<b>1,515</b>

LANDSCAPING ITEMS (SEEDING)

	SEEDING, CLASS 2A (ACRE)	SEEDING MERIC PRAIRIE (ACRE)	SEEDING, SEDGE MEADOW MIX (ACRE)	SEEDING, WETLAND EDGE MIX (ACRE)
STA 911+20- RT	0.35	0.15		0.01
STA 916+30 LT	0.30	0.20		0.10
STA 916+50- RT	0.30	0.25		0.02
STA 921+75 LT	0.30	0.25		0.02
COMPENSATORY STORAGE SITE 1		0.40	0.20	0.30
COMPENSATORY STORAGE SITE 2		0.25		0.30
<b>SUBTOTAL</b>	<b>1.25</b>	<b>1.50</b>	<b>0.25</b>	<b>0.75</b>
<b>APPLICATIONS</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>2</b>
<b>TOTAL</b>	<b>2.50</b>	<b>3.00</b>	<b>0.50</b>	<b>1.50</b>

LANDSCAPING ITEMS

	TOPSOIL FURNISH AND PLACE, 4" (SQ YD)	TOPSOIL FURNISH AND PLACE, 12" (SQ YD)	EROSION CONTROL BLANKET (SQ FT)
STA 911+20- RT	2,387	359	2,387
STA 916+30 LT	2,699		2,699
STA 916+50- RT	2,607		2,607
STA 921+75 LT	2,655		2,655
COMPENSATORY STORAGE SITE 1	3,857		3,857
COMPENSATORY STORAGE SITE 2	2,590		2,590
<b>TOTAL</b>	<b>16,795</b>	<b>359</b>	<b>16,793</b>

EROSION CONTROL ITEMS

	EROSION CONTROL BLANKET (SQ YD)	TEMPORARY EROSION CONTROL SEEDING (POUND)	MULCH, METHOD 2 (ACRE)	CRUSHED AGGREGATE CA-1 (SQ YD)	FILTER FABRIC (SQ YD)	SEDIMENT CONTROL, SILT FENCE (FOOT)	SEDIMENT CONTROL, SILT FENCE MAINTENANCE (FOOT)
STA 911+20- RT	2,590	53.5		9	105	737	737
STA 916+30 LT	2,716	56.1		9	105	938	938
STA 916+50- RT	2,497	51.6		9	105	724	724
STA 921+75 LT	2,593	53.3		9	105	747	747
COMPENSATORY STORAGE SITE 1	2,018	68.7	0.27	9	108	1,164	1,164
COMPENSATORY STORAGE SITE 2	1,375	51.4	0.23	9	108	988	988
<b>TOTAL</b>	<b>14,005</b>	<b>340</b>	<b>0.5</b>	<b>54</b>	<b>636</b>	<b>5,298</b>	<b>5,298</b>

MAINTENANCE OF TRAFFIC ITEMS

	TEMPORARY MODULAR GLARE SCREEN (FOOT)	SHORT-TERM PAVEMENT MARKING (FOOT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 6 "(FOOT)	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)	TEMPORARY PAVEMENT (SQ YD)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2 (EACH)	CHANGEABLE MESSAGE SIGN (CAL MO)
<b>PRE-STAGE</b>														
STA 907+57-STA 911+20			363			121.0								9
STA 911+20-STA 915+60			440			146.7								
STA 915+60-STA 917+19			159			53.0								
STA 917+19-STA 921+75			456			152.0								
STA 921+75-STA 924+07			232			77.3								
<b>STAGE I</b>														
STA 907+15-STA 911+20			1,620	48		540.0	48		2	246	246	1		
STA 911+20-STA 915+60	76		1,346	547			547		22	147	611	1		
STA 915+60-STA 917+19	159		318	318	22		318		13	54	102			
STA 917+19-STA 921+75	73		1,412	578			578		23	152	447	1		
STA 921+75-STA 924+08			932	47		310.7	47		2	199	60	1		
<b>STAGE II</b>														
STA 908+70-STA 911+20			1,000			333.3		47			137		1	
STA 911+20-STA 915+60			1,760			585.3		525			27		1	
STA 915+60-STA 917+19			636			213.3		218						
STA 917+19-STA 921+75			1,824			608.0		602						
STA 921+75-STA 924+08			932			310.7		48			54		1	
<b>RESURFACING STAGE</b>														
STA 921+75-STA 924+08		295												9
<b>TOTAL</b>	<b>308</b>	<b>295</b>	<b>13,430</b>	<b>1,534</b>	<b>22</b>	<b>3,451.3</b>	<b>1,534</b>	<b>1,440</b>	<b>62</b>	<b>798</b>	<b>1,684</b>	<b>4</b>	<b>4</b>	<b>18</b>