

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	SHEET NO. 2
F.A.P. 389	2424.2 B-1	COOK	23	9	16 SHEETS
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT			

Contract No. 60E11

**GENERAL NOTES**

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Concrete repair areas are based on the Underwater Inspection Report dated April 28, 2005. The Engineer shall approve all concrete repair areas and crack sealing prior to commencement of work. Any areas not shown on the plans shall be repaired if directed by the Engineer.

**INDEX OF SHEET**

- 1 General Plan & Elevation
- 2 General Data
- 3 Removal & Staging Plan
- 4 Dolphin Plan & Details
- 5-6 Fender System
- 7 Miscellaneous Details
- 8 East River Pier Repairs
- 9 West River Pier Repairs
- 10 West Dock Wall Repairs
- 11-12 Soil Boring Logs
- 13-16 Existing Plans

**TOTAL BILL OF MATERIAL**

Item	Unit	Super	Sub	Total
Porous Granular Embankment	Cu. Yd.	-	88	88
Epoxy Crack Injection	Foot	-	12	12
Structural Repair of Concrete (Depth Equal To Or Less Than 5 Inches)	Sq. Ft.	-	91	91
Structural Repair of Concrete (Depth Greater Than 5 Inches)	Sq. Ft.	-	33	33
Removal of Existing Timber Fenders	L. Sum	-	1.0	1.0
Fender System	L. Sum	-	1.0	1.0
Remove Existing Timber Pile Dolphins	Each	-	2	2
Dolphins	Each	-	2	2
Navigation Lighting System	L. Sum	-	1.0	1.0

DESIGNED	S. CHELBIAN
CHECKED	A. HAMMAD
DRAWN	S. CHELBIAN
CHECKED	A. HAMMAD

**GENERAL DATA**  
F.A.P. RT. 389 - SEC. 2424.2 B-1  
COOK COUNTY  
STATION 380+68.75  
STRUCTURE NO. 016-2445

