

INDEX OF SHEETS

| <u>SHEET NO.</u> | <u>DESCRIPTION</u> |
|------------------|--|
| 1 | COVER SHEET |
| 2 | INDEX OF SHEETS, STANDARDS AND GENERAL NOTES |
| 3 | SUMMARY OF QUANTITIES |
| 4-7 | BRIDGE REPAIRS |
| 8 | TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10) |

LIST OF STATE STANDARDS

| <u>STANDARD NO.</u> | <u>DESCRIPTION</u> |
|---------------------|--|
| 701426-03 | LANE CLOSURE, MULTI-LANE, INTERMITTENT OR MOVING OPERATION, FOR SPEED > 45 MPH |
| 701606-06 | URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN |
| 701801-04 | LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE |
| 701901-01 | TRAFFIC CONTROL DEVICES |

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND VILLAGE OF LOMBARD.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT 847-705-4151. A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM BRIDGE INSPECTORS

DO NOT SCALE PLAN FOR CONSTRUCTION DIMENSIONS

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

| | | | | | | | | | | |
|--|------------------------|------------|-----------|---|---|-----------------------|-----------------------|---------------------------|----------------------|-------------------|
| FILE NAME = c:\projects\dl53408\design.ee.dgn | USER NAME = abebawa | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES | F.A.P. RTE. 870 | SECTION 2008-044 I | COUNTY DUPAGE | TOTAL SHEETS 8 | SHEET NO. 2 |
| PLOT SCALE = 49,9999' / IN. | PLOT DATE = 10/28/2008 | DRAWN - | CHECKED - | | | | | | | |
| | | DATE - | REVISED - | | SCALE: | SHEET NO. | OF | SHEETS | STA. | TO STA. |
| | | | | | | FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| | | | | | | CONTRACT NO. 60E88 | | | | |