

ROADWAY SIGNING SCHEDULE

SIGN NUMBER	PANEL DESCRIPTION	STATION	OFFSET	EXISTING SIGNING RELOCATIONS			NEW SIGNING				
				RELOCATE SIGN PANEL-TYPE 1	RELOCATE SIGN PANEL ASSEMBLY - TY A	RELOCATED SIGN PANEL ASSEMBLY - TY B	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	METAL POST TYPE A	METAL POST TYPE B	
				SQ FT	EACH	EACH	SQ FT	SQ FT	FOOT	FOOT	
IL ROUTE 23											
	SPEED LIMIT	61+36.22	18.95				7.5		7		
	SPEED LIMIT	61+36.62	21.07				7.5		7		
	SPEED LIMIT	69+84.26	24.59				7.5		7		
	SPEED LIMIT	70+00.83	25.1				7.5		7		
	SPEED LIMIT	88+74.77	24.41				7.5		7		
	SPEED LIMIT	88+82.66	19.44				7.5		7		
	KISHWAUKEE RIVER				1						
	KISHWAUKEE RIVER				1						
TOTALS				0	2	0	45	0	42	0	

DRIVEWAY SCHEDULE

LOCATION	HOT-MIX ASPHALT SURF CSE, MIX "C" N50, 2"	HOT-MIX ASPHALT BSE CSE, 6"	HOT-MIX ASPHALT BSE CSE, 8"	AGGREGATE BASE COURSE TYPE A 8"	CURB CONC TY B	BITUMINOUS MATERIALS (PRIME COAT)	TEMPORARY ACCESS (PRIVATE ENTRANCE)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	TEMPORARY ACCESS (FIELD ENTRANCE)
	TONS	SQ YD	SQ YD	SQ YD	FOOT	GALLON			
IL ROUTE 23									
STA. 60+00.00 (LT)	7.2	0	0	63	64.8	6			1
STA. 60+00.00 (RT)	10.9	0	95	0	64.6	9			1
STA. 62+15.00 (RT)	9.4	0	81	0	73.8	8			1
STA. 63+27.94 (LT)	7.4	0	0	65	76.1	6			1
STA. 73+48.00 (LT)	27.4	0	0	238	0.0	24			1
STA. 83+50.00 (RT)	5.2	45	0	0	0.0	4	1		
STA. 84+40.00 (LT)	21.1	0	184	0	92.4	18			1
STA. 84+40.00 (RT)	9.7	0	84	0	0.0	8			1
STA. 85+20.00 (RT)	9.7	0	85	0	0.0	8			1
STA. 88+50.00 (LT)	14.8	0	129	0	0.0	13			1
Totals	123	45	658	366	372	107	1	6	3

FILE NAME =	USER NAME = #USER#	DESIGNED - GJM	REVISED - 5/13/2008	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - GJM	REVISED - 7/18/2008					324	23B-1	MCHENRY	97	12
PLOT SCALE = #SCALE#		CHECKED - EJL	REVISED - ----		SCALE: NONE	SHEET NO. 3 OF 5 SHEETS	STA. 59+00 TO STA. 89+00	CONTRACT NO. 62892				
PLOT DATE = 9/30/2008		DATE - 3/11/2008	REVISED - ----		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							