HEUER AND ASSOCIATES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
Consulting Engineers	1004	00-00079-01-FP	COOK	46	26
2315 Enterprise Drive - Suite 102 Westchester, IL 60154-5811 708-492-1000	STA. 39+60		TO STA. 45+53.65		
	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
BLUFF AVENUE IMPROVEMENTS DATE: 07/18/08	WATER MAIN IMPROVEMENTS				

CONTRACT No. 63007

MATCHLINE, STA. 39+60
SEE SHEET 25

BASELINE 5

EXISTING R.O.W.

BLUFF AVE.

66' R.O.W.

30.08' F-F

LOT #12

(PARKING)

FRANKLIN AVE.

CALENDAR AVE.

BURLINGTON AVE.

EXISTING R.O.W.

WATER MAIN RELOCATION
TO BE PERFORMED UNDER VILLAGE
OF LA GRANGE BURLINGTON AVENUE
WATER MAIN PROJECT

END OF PROJECT
BLUFF AVENUE
STATION 45+53.65

NOTES:

1. WATER MAIN CONSTRUCTION AT CALENDAR AVENUE AND NORTH OF CALENDAR AVENUE PERFORMED UNDER SEPARATE VILLAGE OF LA GRANGE BURLINGTON AVENUE WATER MAIN PROJECT

SCALE:
1"=20' H
1"=2' V

EXISTING CENTERLINE

PROFOSED ROADWAY CROWN LINE

EXISTING 6" GAS

EXISTING 12" WATER MAIN

EXISTING CENTERLINE ELEVATION

STATION	39+50	40+00	40+50	41+00	41+50	42+00	42+50	43+00	43+50	44+00	44+50	45+00	45+50
EXISTING CENTERLINE ELEVATION	627.73CL	627.72CL	627.72CL	627.82CL	627.99CL	628.00CL	628.09CL	628.12CL	628.20CL	628.26CL	628.40CL	628.47CL	629.11CL

00-Bluff.dgn 26-Watermain_at_Burlington 7/18/2008 2:30:49 PM