

F. A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
846	05-00047-00-CH	WILL	036	003
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT #63033

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					1000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031-1F	Y080
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30						
	20100500	TREE REMOVAL, ACRES	ACRE	0.42	0.42						
	20101200	TREE ROOT PRUNING	EACH	7	7						
	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	3	3						
	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	4	4						
	20200100	EARTH EXCAVATION	CU YD	3420	3420						
	20200200	ROCK EXCAVATION	CU YD	100	100						
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	330	330						
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	330	330						
	20800150	TRENCH BACKFILL	CU YD	99	99						
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4280	4280						
	25000210	SEEDING, CLASS 2A	ACRE	0.88	0.88						
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	79	79						
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	79	79						
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	79	79						
	25100630	EROSION CONTROL BLANKET	SQ YD	4280	4280						
	28000300	TEMPORARY DITCH CHECKS	EACH	1	1						
	28000400	PERIMETER EROSION BARRIER	FOOT	3000	3000						
	28000500	INLET AND PIPE PROTECTION	EACH	9	9						
	28000510	INLET FILTERS	EACH	4	4						
	28100101	STONE RIPRAP, CLASS A1	SQ YD	305	305						
	28100107	STONE RIPRAP, CLASS A4	SQ YD	305	305						
	28200200	FILTER FABRIC	SQ YD	305	305						
	35501327	HOT-MIX ASPHALT BASE COURSE, 10 3/4"	SQ YD	2879	2879						
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1154	1154						
	40600300	AGGREGATE (PRIME COAT)	TON	12	12						
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1	1						
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL -- BUTT JOINT	SQ YD	272	272						
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1292	1292						
	44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	8860	8860						
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	77	77						
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	290	290						
	44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	40	40						
	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1023	1023						
	54213471	END SECTIONS 36"	EACH	2	2						
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1						
	54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	1	1						
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	7	7						
	550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	667	667						
	55100700	STORM SEWER REMOVAL 15"	FOOT	555	555						
	552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	70	70						
	60107600	PIPE UNDERDRAINS 4"	FOOT	435	435						
	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1						
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1						
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2						
	60500050	REMOVING CATCH BASINS	EACH	3	3						
	60602400	CONCRETE GUTTER (SPECIAL)	FOOT	26	26						
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	161	161						

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL RTE 53 AT UNIVERSITY PARKWAY INTERSECTION IMPROVEMENT SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE: 8-29-08

DRAWN BY: RG
CHECKED BY: WD

ROBINSON ENGINEERING, LTD.
17000 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473
(708) 591-6700 FAX (708) 591-9828
ILLINOIS DESIGN FIRM REGISTRATION NO. 154001208 04161_02 QUAN-01