

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00081-00-BR	LAKE	26	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NUMBER	PAY ITEM	UNITS	Total Quantity	Wimot Road	Hazel Avenue
				S/N 049-6151 X080-2A	S/N 049-6152 X080-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	40	20	20
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16		16
28000400	PERIMETER EROSION BARRIER	FOOT	1117	565	552
40600100	BITUMINOUS MATERIALS, PRIME COAT	GAL	10	10	
40600625	LEVELING BINDER (MACHINE METHOD) N-50	TON	4	4	
40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	17	17	
40603335	HOT MIX ASPHALT SURFACE COURSE MIX "D" N50	TON	9	9	
42001165	BRIDGE APPROACH PAVEMENT	SQ. YD.	381	201	180
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ. YD.	76	40	36
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5" INCH	SQ. FT.	400	200	200
44000100	PAVEMENT REMOVAL	SQ. YD.	433	241	192
44000198	HOT MIX ASPHALT SURFACE REMOVAL - VARIABLE DEPTH	SQ. YD.	83	83	
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	324	164	160
44000600	SIDEWALK REMOVAL	SQ. FT.	360	200	160
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2	1	1
50102400	CONCRETE REMOVAL	CU. YD.	6	1.0	5.0
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	58	22	36
50300260	BRIDGE DECK GROOVING	SQ. YD.	224	109	115
50300300	PROTECTIVE COAT	SQ. YD.	803	391	412
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT.	1383	1383	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ. FT.	1565		1565
50800205	REINFORCEMENT BARS, EPOXY COATED	POUNDS	8390	3360	5030
51500100	NAME PLATES	EACH	2	1	1
58700300	CONCRETE SEALER	SQ. FT.	354	142	212
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EA	1	1	
60300105	FRAME AND GRATES TO BE ADJUSTED	EA	3	1	2
60300305	FRAME AND LIDS TO BE ADJUSTED	EA	1	1	
60404300	FRAME AND GRATES, TYPE 3	EA	3	1	2
60406000	FRAME AND LIDS, TYPE 1, OPEN LID	EA	1	1	
60603800	COMBINATION CONCRETE CURB & GUTTER TYPE B-6.12	FOOT	120	96	24
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	80	40	40
67000500	ENGINEERS FIELD OFFICE TYPE B	CAL. MO.	4	2	2
67100100	MOBILIZATION	L. SUM	1	0.5	0.5
70102550	TRAFFIC CONTROL & PROTECTION-TEMPORARY DETOUR	EA	2	1	1
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH LESS THAN OR EQUAL TO 5) INCHES	SQ. FT.	223	152	71.0
X0325670	CONCRETE BRIDGE RAIL, SIDEWALK MOUNTED	FOOT	159	66	93
X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	244	117	127
Z0073700	TEMPORARY WALL BRACING SYSTEM	L. SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	11		11

PLAN	DATE
BY	
REVISIONS	
PLOTTED	
ALIGNMENT CHECKED	
NOTE BOOK	
NO.	
CADD FILE NAME	

PROFILE	DATE
BY	
REVISIONS	
PLOTTED	
GRADES CHECKED	
NOTE BOOK	
NO.	
STRUCTURE NOTATIONS CHECKED	

REVISIONS	
NAME	DATE

URS 100 SOUTH WACKER DRIVE TEL (312) 939-1000
 SUITE 500 CHICAGO, IL 60606 FAX (312) 939-4198

VILLAGE OF DEERFIELD

**SUMMARY OF QUANTITIES
WILMOT & HAZEL BRIDGE**

SCALE: VERT. NONE
 HORIZ. 1"=50'
 DATE: 9/12/2008

DRAWN BY: MIA
 CHECKED BY: MHL