

HMA SCHEDULE

LOCATION		PAVT LENGTH	PAVT WIDTH	PAVEMENT AREA	40600200	40600300	40600625	40600982	40600990	40603310	40800050	44000158	44000198	48101200	70300100	70301000	
					BIT. PRIME 2 APPL	AGG. PRIME 1 APPL	LEVELING BINDER (MACHINE METHOD), N50	HMA SURF REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURF CRSE MIX "C", N50 1-1/2"	HMA SURF CRSE MIX "C", N50 2-1/4"	INCIDENTAL HOT MIX SURFACING	HMA SURFACE REMOVAL 2-1/4"	HMA SURF REM VARIABLE DEPTH	AGGREGATE SHOULDERS, TYPE B	SHORT TERM PAVEMENT MARKINGS	WORK ZONE PAVE MARK REMOVAL
STATIONING		(FT.)	(FT.)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(FT.)	(SQ FT)
308+45	TO 308 + 92	47	26	136	0.10	0.2	7.6			11.4	5.3				14.1	1.6	
308+92	TO 309 + 76	84	26	243	0.16	0.4	13.6			20.4	4.7			5.3	25.2	2.8	
309+76	TO 312 + 66	290	26	838	0.48	1.3	46.9			70.4				36.7	87.0	9.7	
312+66	TO 313 + 60	94	26	272	0.16	0.4	15.2			22.8		135.8		11.9	28.2	3.1	
313+60	TO 328 + 00	1440	26	4160	2.38	6.2	233.0			349.4		4160.0		182.2	432.0	48.0	
328+00	TO 336 + 30	830	26	2398	1.37	3.6	134.3			201.4				105.0	249.0	27.7	
336+30	TO 349 + 50	1320	26	3813	2.18	5.7	213.5			320.3		3813.3		167.0	396.0	44.0	
349+50	TO 363 + 20	1370	26	3958	2.26	5.9	221.6			332.5		1978.9		173.4	411.0	45.7	
363+20	TO 373 + 30	1010	26	2918	1.67	4.4	163.4			245.1		2917.8		127.8	303.0	33.7	
373+30	TO 375 + 50	220	26	636	0.36	1.0	35.6			53.4		317.8		27.8	66.0	7.3	
375+50	TO 386 + 08	1058	26	3056	1.75	4.6	171.2			256.7				133.9	317.4	35.3	
386+08	TO 390 + 72	464	26	1340	1.00	2.0	75.1			112.6	52.0				139.2	15.5	
390+72	TO 393 + 10	238	26	688	0.39	1.0	38.5			57.8				30.1	71.4	7.9	
393+10	TO 395 + 90	280	26	809	0.46	1.2	45.3			67.9		404.4		35.4	84.0	9.3	
395+90	TO 416 + 18	2028	26	5859	3.37	8.8	328.1			492.1		5858.7		256.6	608.4	67.6	
416+18	TO 416 + 70	52	26	150	0.09	0.2	8.4			12.6	5.8			150.2	15.6	1.7	
416+70	TO 417 + 15	45	32.5	163	0.09	0.2	9.1			13.7							
417+15	TO 417 + 68	53	26	153	0.11	0.2	8.6			12.9	5.9			153.1	15.9	1.8	
417+68	TO 418 + 33	65	26	188	0.13	0.3	10.5			15.8	7.3			93.9	19.5	2.2	
418+33	TO 424 + 60	627	26	1811	1.04	2.7	101.4			152.2				905.7	79.3	188.1	
424+60	TO 449 + 00	2440	26	7049	4.03	10.6	394.7			592.1		7048.9		308.8	732.0	81.3	
449+00	TO 473 + 70	2470	26	7136	4.08	10.7	399.6			599.4		3567.8		312.6	741.0	82.3	
473+70	TO 479 + 64	594	26	1716	0.98	2.6	96.1			144.1				75.2	178.2	19.8	
479+64	TO 489 + 36	972	26	2808	2.10	4.2	157.2			235.9	108.9			295.2	291.6	32.4	
489+36	TO 491 + 70	234	26	676	0.39	1.0	37.9			56.8				29.6	70.2	7.8	
491+70	TO 496 + 94	524	26.5	1543	0.88	2.3	86.4			129.6		1542.9		33.2	157.2	17.5	
496+94	TO 501 + 30	436	26	1260	0.72	1.9	70.5			105.8			629.8	55.2	130.8	14.5	
501+30	TO 504 + 70	340	26	982	0.56	1.5	55.0			82.5				43.0	102.0	11.3	
504+70	TO 508 + 00	330	26	953	0.55	1.4	53.4			80.1			476.7	41.8	99.0	11.0	
508+00	TO 516 + 30	830	26	2398	1.37	3.6	134.3			201.4				105.0	249.0	27.7	
516+30	TO 525 + 25	895	26	2586	1.48	3.9	144.8			217.2			1292.8	113.3	268.5	29.8	
525+25	TO 541 + 03	1578	26	4559	2.61	6.8	255.3			382.9				199.7	473.4	52.6	
541+03	TO 550 + 02	899	26.5	2647	1.51	4.0	148.2			222.4		2647.1		56.9	269.7	30.0	
550+02	TO 551 + 63	161	26	465	0.35	0.7	26.0	72.2	12.1	39.1	18.0				48.3	5.4	
551+63	TO 552 + 76	113															
552+76	TO 554 + 30	154	26	445	0.33	0.7	24.9	72.2	12.1	37.4	17.2				46.2	5.1	
554+30	TO 555 + 00	70	26.5	206	0.14	0.3	11.5			17.3	3.9	206.1			21.0	2.3	
555+00	TO 561 + 12	612	26.5	1802	1.03	2.7	100.9			151.4		1802.0		38.7	183.6	20.4	
561+12	TO 576 + 30	1518	26	4385	2.51	6.6	245.6			368.4			2192.7	192.1	455.4	50.6	
576+30	TO 578 + 00	170	26	491	0.28	0.7	27.5			41.3				21.5	51.0	5.7	
WEST LOTT ROAD		57	22	151	0.04	0.2		44.0	12.2					21.2			
EAST BUTZ ROAD		65	22	163	0.05	0.2		44.0	12.2					22.8			
WEST HERSHEY HIGHWAY		27	22	108	0.03	0.2		44.0	12.2					15.1			
EAST HERSHEY HIGHWAY		22	22	97	0.03	0.1		44.0	12.2					13.5			
WEST SABIN CHURCH RD		27	24	117	0.03	0.2		48.0	13.3					16.4			
EAST SABIN CHURCH RD		27	24	156	0.04	0.2		48.0	13.3					21.8			
WEST LORAN ROAD		22	54	215	0.06	0.3		108.0	30.0					30.1			
EAST LORAN ROAD		27	22	116	0.03	0.2		44.0	12.2					16.2			

FILE NAME =	USER NAME = doasdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 73	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\pwwork\pwwid01\DOSSDD\dms33571\082977\vr.dgn		DRAWN -	REVISED -			654	*	STEPHENSON	89	20	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64C91					
PLOT DATE = Fri Oct 03 08:37:22 2008		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					