

HMA SCHEDULE

LOCATION		PAVT LENGTH	PAVT WIDTH	PAVEMENT AREA	40600200	40600300	40600625	40600982	40600990	40603310		40800050	44000158	44000198	48101200	70300100	70301000
					BIT. PRIME 2 APPL	AGG. PRIME 1 APPL	LEVELING BINDER (MACHINE METHOD), N50	HMA SURF REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURF CRSE MIX "C", N50 1-1/2"	HMA SURF CRSE MIX "C", N50 2-1/4"	INCIDENTAL HOT MIX SURFACING	HMA SURFACE REMOVAL 2-1/4"	HMA SURF REM VARIABLE DEPTH	AGGREGATE SHOULDERS, TYPE B	SHORT TERM PAVEMENT MARKINGS	WORK ZONE PAVE MARK REMOVAL
STATIONING	DESCRIPTION	(FT.)	(FT.)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(FT.)	(SQ FT)
BLOCK ROAD		22	22	81	0.02	0.1		44.0	12.2			11.3					
WALGREN RD		22	26	130	0.04	0.2		52.0	14.4			18.1					
WEST SOUTH ST		12	30	45	0.01	0.1		16.7	16.7			6.3	45.3				
EAST SOUTH ST		15	34	60	0.02	0.1		18.9	18.9			8.4	60.0				
WEST DEVORE ST		13	48	78	0.02	0.1		26.7	26.7			10.9	78.0				
EAST DEVORE ST		11	46	68	0.02	0.1		25.6	25.6			9.5	67.8				
WEST NORTH ST		15	36	73	0.02	0.1		20.0	20.0			10.3	73.3				
EAST NORTH ST		8	28	31	0.01	0.0		15.6	15.6			4.4	31.1				
PEARL CITY ROAD	MAINLINE: MILL & PAVE 26' RT							15.9	15.9								
CENTER ST		22	20	68	0.02	0.1		11.1	11.1			9.6	68.4				
JOHN ST		8	20	26	0.01	0.0		11.1	11.1			3.6	25.8				
GOLDMINE RD		18	36	72	0.02	0.1		20.0	20.0			10.1	72.0				
MILL ST		28	37	129	0.04	0.2		20.6	20.6			18.1	129.1				
GREEN ST		13	22	43	0.01	0.1		12.2	12.2			6.1	43.3				
WEST GRANT ST		12	20	33	0.01	0.0		11.1	11.1			4.7	33.3				
EAST GRANT ST		17	8	27	0.01	0.0		4.4	4.4			3.7	26.7				
GARFIELD RD		14	21	47	0.01	0.1		11.7	11.7			6.5	46.7				
700N		22	12	59	0.02	0.1		6.7	6.7			8.2					
WEST DUBLIN ROAD		22	73	414	0.12	0.6		44.0	40.6			57.9					
EAST DUBLIN ROAD		22	36	136	0.04	0.2		44.0	20.0			19.0					
WEST RADERS RD		22	24	109	0.03	0.2		44.0	13.3			15.2					
EAST RADERS RD		22	24	105	0.03	0.2		44.0	13.3			14.7					
WEST MOUND RD		22	24	98	0.03	0.1		44.0	13.3			13.7					
EAST MOUND RD		22	25	97	0.03	0.1		44.0	13.9			13.6					
WEST DAMEIER RD		22	22	112	0.03	0.2		44.0	12.2			15.7					
EAST DAMEIER RD		28	27	150	0.04	0.2		56.0	15.0			21.0					
TOTALS					98.5	257.3	9469.0	1245.1	638.2	14124.6	327.7	477.8	30633.6	36831.6	6294.6	17194.8	1910.5

*NOTE: ADDITIONAL QUANTITIES HAVE BEEN PROVIDED FOR SAG CORRECTION. SEE TABLE FOR ADDITIONAL INFORMATION

FILE NAME =	USER NAME = doasdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 73	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et\piv_work\PWIDOT\DOSSDD\dms33571\02297	7crr.dgn	DRAWN -	REVISED -			654	*	STEPHENSON	89	21	
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 64C91					
	PLOT DATE = Fri Oct 03 08:38:59 2008	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					