

# PATCHING SCHEDULE

13FOOT LANE WIDTH

7FOOT LANE WIDTH FOR 1/2 LANE PATCH

STATION	REMARKS	LENGTH OF PATCH		AREA OF CLASS B PATCHES, 14"								HMA REMOVAL OVER PATCHES 7"		HMA REPLACEMENT OVER PATCHES, 7"	
		LT LANE (feet)	RT LANE (feet)	TYPE 1		TYPE 2		TYPE 3		TYPE 4		LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (tons)	RT LANE (tons)
				LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)	LT LANE (sq yd)	RT LANE (sq yd)				
406 + 80		42	42							60.7	60.7	62.0	62.0	24.29	24.29
407 + 50		25	12						17.3	36.1		37.4	18.6	14.67	7.30
407 + 84		19	6				8.7			27.4		28.7	10.0	11.27	3.91
409 + 49		6	6			8.7	8.7					10.0	10.0	3.91	3.91
410 + 4		6	18			8.7					26.0	10.0	27.3	3.91	10.70
412 + 28		20	20							28.9	28.9	30.2	30.2	11.83	11.83
413 + 90		6	6			8.7	8.7					10.0	10.0	3.91	3.91
418 + 25		6	6			8.7	8.7					10.0	10.0	3.91	3.91
421 + 55		6	6			8.7						10.0		3.91	
422 + 22		16	6				8.7	23.1				24.4	10.0	9.57	3.91
423 + 1		6	6			8.7	8.7					10.0	10.0	3.91	3.91
424 + 50		100	100							144.4	144.4	145.7	145.7	57.13	57.13
426 + 13		40	40							57.8	57.8	59.1	59.1	23.16	23.16
428 + 62		6	6			8.7	8.7					10.0	10.0	3.91	3.91
430 + 55		7	7			10.1	10.1					11.4	11.4	4.47	4.47
433 + 26		6	6			8.7	8.7					10.0	10.0	3.91	3.91
434 + 54		20	20							28.9	28.9	30.2	30.2	11.83	11.83
436 + 33		6	6			8.7	8.7					10.0	10.0	3.91	3.91
437 + 75		6	6			8.7						10.0		3.91	
439 + 43		6	6			8.7	8.7					10.0	10.0	3.91	3.91
440 + 93		6	6			8.7	8.7					10.0	10.0	3.91	3.91
442 + 20		100	100							144.4	144.4	145.7	145.7	57.13	57.13
444 + 10		140	140							202.2	202.2	203.5	203.5	79.78	79.78
445 + 35		20	20							28.9	28.9	30.2	30.2	11.83	11.83
445 + 90		10	10			14.4	14.4					15.7	15.7	6.17	6.17
446 + 25		6	6			8.7	8.7					10.0	10.0	3.91	3.91
447 + 4		6	6			8.7	8.7					10.0	10.0	3.91	3.91
453 + 5		6	6			8.7	8.7					10.0	10.0	3.91	3.91
454 + 82		15	15					21.7	21.7			23.0	23.0	9.00	9.00
455 + 56		6	6			8.7	8.7					10.0	10.0	3.91	3.91
456 + 30		6	6			8.7	8.7					10.0	10.0	3.91	3.91
458 + 90		6	6			8.7	8.7					10.0	10.0	3.91	3.91
463 + 13		12	12					17.3	17.3			18.6	18.6	7.30	7.30
465 + 53			6				8.7						10.0		3.91
470 + 39		6	6			8.7						10.0		3.91	
470 + 76		6	6			8.7	8.7					10.0	10.0	3.91	3.91
471 + 98		6	6			8.7	8.7					10.0	10.0	3.91	3.91
478 + 60		6	6			8.7						10.0		3.91	
499 + 40		22	6				8.7			31.8		33.1	10.0	12.97	3.91

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 73</b>	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.P. RTE. 654	SECTION *	COUNTY STEPHENSON	TOTAL SHEETS 89	SHEET NO. 27	CONTRACT NO. 64C91
ct:\pw_work\NPWIDOT\DOSSDD\dms33571\d02977crr.dgn		DRAWN -	REVISED -											
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -											
PLOT DATE = Wed Sep 24 07:51:32 2008		DATE -	REVISED -											