

GENERAL NOTES

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ONLY THOSE TREES DESIGNATED BY THE ENGINEER OR LISTED IN THE TREE REMOVAL SCHEDULE SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

MEMBERS OF JULIE KNOWN TO BE WITHIN LIMITS OF IMPROVEMENT ARE:

- COMMONWEALTH EDISON
- AT & T
- COMCAST
- NICOR GAS

COMMITMENTS

HISTORIC DOCUMENTATION FOR HOUSE AT 404 JEFFERSON STREET:  
 MARK BRANSTNER, HISTORIC ARCHAEOLOGIST, WITH THE ILLINOIS TRANSPORTATION ARCHAEOLOGICAL RESEARCH PROGRAM (ITARP) SHALL BE CONTACTED WHEN A DATE HAS BEEN DECIDED FOR ACTUAL DEMOLITION OF THE HOUSE. TWO WEEKS OF HISTORICAL DOCUMENTATION WORK WILL BE REQUIRED PRIOR TO THE DEMOLITION. NOTIFICATION SHOULD ALLOW ENOUGH LEAD TIME FOR ITARP TO SCHEDULE THEIR WORK. ITARP SHALL BE NOTIFIED IF THE DATE OF THE DEMOLITION CHANGES.

MARK BRANSTNER, RPA  
 HISTORIC ARCHEOLOGIST  
 PHONE: 217-244-0892  
 FAX: 217-244-7458  
 CELL: 517-927-4556  
 mbranstn@illinois.edu

100% STATE

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION CODE TYPE:	
		UNIT	Y004 TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	44
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1425
* 25000200	SEEDING, CLASS 2	ACRE	0.3
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26
* 25100115	MULCH, METHOD 2	ACRE	0.3
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30
67100100	MOBILIZATION	L SUM	1
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1
* Z0049803	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 3	L SUM	1
* Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1
* Z0049903	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 3	L SUM	1

\* SPECIALTY ITEMS

BUILDING NUMBER (PARCEL #)	TOPSOIL & SEEDING					
	TOPSOIL FURNISH AND PLACE 4"	SEEDING CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2
	SQ YD	ACRE	TON	TON	TON	ACRE
1 (3KC0053)	612	0.13	11	11	11	0.13
2 (3KC0086)	417	0.09	8	8	8	0.09
3 (3KC0052)	396	0.08	7	7	7	0.08
TOTALS	1425	0.30	26	26	26	0.30

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION  
 DISTRICT THREE

PREPARED BY: *Richard Powell*  
 DISTRICT STUDIES & PLANS ENGINEER  
 DATE: 10-20-08

EXAMINED BY: *Herbert*  
 DISTRICT CONSTRUCTION ENGINEER  
*Wayne S. Piller*  
 DISTRICT MATERIALS ENGINEER  
*Bruce A. Huchen*  
 DISTRICT OPERATIONS ENGINEER