

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE												
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 80% FEDERAL 20% STATE	STRUCTURE X371-58 80% FEDERAL 20% STATE	ROADWAY 1000-2A 100% COUNTY	SIGNALS Y031-IF 80% FEDERAL 20% STATE	LIGHTING Y030-IE 80% FEDERAL 20% STATE							
44000100	PAVEMENT REMOVAL	SO YD	2326.5	2326.5											
44000157	HOT - MIX ASPHALT SURFACE REMOVAL, 2 "	SO YD	14057.6	14057.6											
44000198	HOT - MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	233.3	233.3											
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1896	1896											
44000700	APPROACH SLAB REMOVAL	SO YD	186.6	186.6											
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SO YD	2,267.2	2,267.2											
44002500	GUTTER OUTLET REMOVAL	EACH	4	4											
44002805	ISLAND REMOVAL	SO FT	1810	1810											
44003000	MEDIAN REMOVAL	FOOT	455	455											
44004000	PAVED DITCH REMOVAL	FOOT	36	36											
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	1214.8	1214.8											
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	44	44											
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	87	87											
44213200	SAW CUTS	FOOT	5767	5767											
48101200	AGGREGATE SHOULDERS, TYPE B	TON	441.4	441.4											
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SO YD	169.8	169.8											
48203037	HOT - MIX ASPHALT SHOULDERS, 10"	SO YD	901.9	901.9											
48203100	HOT - MIX ASPHALT SHOULDERS	TON	1,739.2	1,708			31.2								
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1											
50157300	PROTECTIVE SHIELD	SO YD	106	106											
50200100	STRUCTURE EXCAVATION	CU YD	530	530											
50300225	CONCRETE STRUCTURES	CU YD	444.7	444.7											
50300255	CONCRETE SUPER STRUCTURES	CU YD	704.9	704.9											
50300260	BRIDGE DECK GROOVING	SO YD	2273	2273											
50300280	CONCRETE ENCASEMENT	CU YD	12	12											
50300300	PROTECTIVE COAT	SO YD	2658	2658											
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1											
50500505	STUD SHEAR CONNECTORS	EACH	8100	8100											
50800105	REINFORCEMENT BARS	POUND	32900	32900											
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	230270	230270											
50800515	BAR SPLICERS	EACH	1427	1427											
51201400	FURNISHING STEEL PILES HP10X42	FOOT	1356	1356											
51202305	DRIVING PILES	FOOT	1356	1356											

• SPECIALTY ITEMS

FILE NAME c:\projects\hormhw\misc.dgn	USER NAME eversci	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 6758	SECTION (1-R),(1-VCIBR)	COUNTY PEORIA	TOTAL SHEETS 192	SHEET NO. 6
PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -	CONTRACT NO. 68092							
PLOT DATE = 10/20/2008	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							