

SCHEDULE OF QUANTITIES

LOCATIONS STA. to STA.	HMA SURF CSE MIX "D" N50	HMA SURF REM	BIT MAT (PRIME COAT)	LEVELING BINDER (HAND METHOD), N50
Bridge Deck	TON	SQ YD	GALLON	TON
269+94 to 270+72	7.0	9.1	1.1	3.0
TOTAL	7.0	9.1	1.1	3.0

Note: Additional leveling binder quantity provided for scratch passes at beam ends to compensate for beam camber.

LOCATIONS STA. to STA.	P P CONC DECK BEAM (33' DEPTH)	REM OF EXIST P P CONC DECK BEAMS
Bridge Deck	SQ FT	SQ FT
269+94 to 270+72	232.5	239.2
TOTAL	232.5	239.2

LOCATIONS STA. to STA.	WATERPROOFING MEMBRANE SYSTEM
Bridge Deck	SQ YD
269+94 to 270+72	35.7
TOTAL	35.7

LOCATIONS STA. to STA.	P C MORTAR FAIRING COURSE
Bridge Deck	FOOT
269+94 to 270+72	159.5
TOTAL	159.5

LOCATIONS STA. to STA.	PAVEMENT MARKING REMOVAL
	SQ FT
Edgeline 268+83 to 271+83	100.0
Center skips 267+29 to 268+83	13.2
271+83 to 273+43	13.2
No Passing Stripe 272+37 to 273+43	35.0
TOTAL	161.4

LOCATIONS STA. to STA.	PAVEMENT MARKING TAPE, TYPE III, 4"
	FOOT
RT Edgeline 267+39 to 272+83	544.0
LT Edgeline 268+83 to 271+83	300.0
STOP BARS	144.0
TOTAL	988.0

LOCATIONS STA. to STA.	SHORT - TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	FOOT	SQ FT
267+29 to 273+43	160	384.6
TOTAL	160	384.6

LOCATIONS STA. to STA.	TEMPORARY CONCRETE BARRIER
	FOOT
269+19 to 271+47	237.5
TOTAL	237.5

LOCATIONS STA. to STA.	IMPACT ATT TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	TEMPORARY RUMBLE STRIP
	EACH	EACH
Jobsite	2	6
TOTAL	2	6

LOCATIONS STA. to STA.	PAINT PAVEMENT MARKING LINE 4"
	FOOT
White Edgeline 268+83 to 271+83	302.0
Yellow skipdash 267+29 to 273+43	160.0
Yellow solid no passing stripe 272+37 to 273+43	106.0
TOTAL	568.0

LOCATIONS STA. to STA.	MOBILIZATION	T C & PROT STANDARD 701321	CHANGEABLE MESSAGE SIGN	TEMPORARY BRIDGE TRAFFIC SIGNAL
	L SUM	EACH	CAL DA	EACH
Jobsite	1	1	14	1
TOTAL	1	1	14	1