

# SUMMARY OF QUANTITIES

100% STATE SFTY - 2A  
HENDERSON

CODE NO.	ITEM	UNIT	RURAL	TOTAL
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	34.4	34.4
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQYD	22	22
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQFT	2402	2402
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	201	201
58100200	WATERPROOFING MEMBRANE SYSTEM	SQYD	285.3	285.3
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	869	869
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1965	1965
70301000	WORKZONE PAVEMENT MARKING REMOVAL	<i>SQ FT</i>	1965	1965

SN. 036-0028 US. 34  
over S.Henderson Crk.

FILE NAME = SN. 036-0028  
\*FILE: S:\GEN\DRAWING\STD&PLNS\SQUAD14  
BRIDGE CONTRACTS\Emergency PPC Beam  
Repair\68849 SN.036-0028 US34 over  
S.HendersonCrk.dgn

USER NAME = #USER*	DESIGNED - ---	REVISED - ---
PLOT SCALE = #SCALE*	CHECKED - ---	REVISED - ---
PLOT DATE = #DATE*	DATE - ---	REVISED - ---

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	(GBR-1)I	HENDERSON	3	3
EMERGENCY BEAM REPLACEMENT			CONTRACT NO. 68849	
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				