



SECTION A-A  
(PR RETAINING WALL)

POINT	STATION	OFFSET (RT)	ELEV	
1	10+21.78	40.35	585.74	
2	10+23.27	35.22	585.85	
3	10+24.91	34.01	585.91	
4	10+29.94	33.47	586.04	
5	10+24.90	35.09	585.91	
6	10+25.00	40.10	586.00	
7	10+30.05	38.33	586.06	
8	10+25.00	42.38	586.06	
9	10+30.98	42.39	586.14	
10	10+27.99	48.38	586.60 *	
11	10+39.09	40.13	586.85	
12	10+30.98	48.39	586.72 *	
13	10+37.20	42.19	586.73	
14	10+45.41	41.94	587.69 *	-TOP OF WALL
15	10+42.00	42.04	587.75	-TOP OF WALL
16	10+31.32	51.91	588.47	-TOP OF WALL
17	10+31.32	52.81	588.54	-TOP OF WALL

\* GRADES ARE TO BE ADJUSTED TO MATCH FIELD CONDITIONS

NOTE

IT IS ANTICIPATED THAT ADDITIONAL CONCRETE WILL BE NEEDED TO POUR THE SIDEWALK OVER THE ADJUSTED INLET LID. THIS COST SHALL BE INCLUDED IN THE COST OF THE SIDEWALK AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.