

Structure
SN 086-0001
80% Fed
20% State

Pay Code	Item	Units	Total	SFTY-2A
50102400	CONCRETE REMOVAL	CU YD	14.7	14.7
50157300	PROTECTIVE SHIELD	SQ YD	54	54
50300255	CONCRETE SUPERSTRUCTURE	CU YD	14.1	14.1
50300300	PROTECTIVE COAT	SQ YD	57	57
50501130	STRUCTURAL STEEL REPAIR	POUND	1,690	1,690
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING	L SUM	1	1
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,890	2,890
52000220	FINGER PLATE EXPANSION JOINT, 6"	FOOT	95	95
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	2000	2000
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	526	526
X0326233	TRAFFIC CONTROL GATE REPLACEMENT, NO. 1	L SUM	1	1
X0326234	TRAFFIC CONTROL GATE REPLACEMENT, NO. 2	L SUM	1	1
X0326235	DOLPHIN REPAIR NO. 1	L SUM	1	1
X0326236	DOLPHIN REPAIR NO. 2	L SUM	1	1

RESIDUES }

** Specialty Items*

FILE NAME =	USER NAME = laughlznr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\LAUGHLINRL\dms77247\ht-500.dgn		DRAWN -	REVISED -		757	20 BR-2	SCOTT	30	3				
PLOT SCALE = 100.0000 ' / IN.		CHECKED -	REVISED -						CONTRACT NO. 72C39				
PLOT DATE = Nov-12-2008 10:13:07AM		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		