

PAVING SCHEDULE

STATION TO STATION	LENGTH FEET	PAVEMENT WIDTH FEET	AREA SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	HMA SURFACE COURSE, MIX "C", N70 TON	HMA SURFACE COURSE, MIX "D", N90 TON	LEVELING BINDER (MACHINE METHOD), N70 TON	LEVELING BINDER (MACHINE METHOD), N90 TON	HMA SURFACE REMOVAL - BUTT JOINT SQ YD	HMA SURFACE REMOVAL, 1/2 SQ YD	HMA SURFACE REMOVAL, 2 1/4 SQ YD	HMA SURFACE REMOVAL, VARIABLE DEPTH SQ YD	AGGREGATE SHOULDERS, TYPE B TON	TEMPORARY RAMP (SPECIAL) SQ YD	TEMPORARY RAMP SQ YD
67+21.00 TO 59+10.00	811.0	36.0	3244.0	324.4	6.5	-	272.5	-	136.2	-	3244.0	-	-	54.7	-	-
59+10.00 TO 56+43.00	267.0	48.0	1424.0	142.4	2.8	-	119.6	-	59.8	-	1424.0	-	-	18.0	-	-
56+43.00 TO 55+80.00	63.0	88.0	616.0	61.6	1.2	-	51.7	-	25.9	185.0	616.0	-	-	4.3	-	51.4
55+80.00 TO 55+40.00	40.0	53.0	235.6	23.6	0.5	-	19.8	-	9.9	-	235.6	-	-	2.7	-	-
55+40.00 TO 46+04.00	936.0	36.0	3744.0	374.4	7.5	-	314.5	-	157.2	-	3744.0	-	-	63.2	-	-
46+04.00 TO 44+90.00	114.0	48.0	608.0	60.8	1.2	-	51.1	-	25.5	-	608.0	-	-	7.7	-	-
44+90.00 TO 43+58.00	132.0	53.0	777.3	77.7	1.6	-	65.3	-	32.6	-	777.3	-	-	8.9	-	-
43+58.00 TO 43+10.00	48.0	59.0	314.7	31.5	0.6	-	26.4	-	13.2	150.0	314.7	-	-	3.2	-	41.7
43+10.00 TO 30+72.00	1238.0	36.0	4952.0	495.2	9.9	-	416.0	-	208.0	-	4952.0	-	-	83.6	-	-
30+72.00 TO 28+70.00	202.0	48.0	1077.3	107.7	2.2	-	90.5	-	45.2	-	1077.3	-	-	13.6	-	-
28+70.00 TO 28+07.00	63.0	46.0	322.0	32.2	0.6	-	27.0	-	13.5	-	322.0	-	-	4.3	-	-
28+07.00 TO 21+50.00	657.0	36.0	2628.0	262.8	5.3	-	220.8	-	110.4	-	2628.0	-	-	44.3	-	-
1292+98.00 TO 1294+80.30	182.3	42.0	850.7	85.1	1.7	-	71.5	-	35.7	-	850.7	-	-	12.3	-	-
1294+80.30 TO 1296+80.30	200.0	50.0	1111.1	111.1	2.2	-	93.3	-	46.7	-	1111.1	-	-	13.5	-	-
1296+80.30 TO 1297+27.80	47.5	55.0	290.3	29.0	0.6	-	24.4	-	12.2	-	290.3	-	-	3.2	-	-
1297+27.80 TO 1308+01.50	1073.7	40.0	4772.0	477.2	9.5	-	400.8	-	200.4	-	4772.0	-	-	72.5	-	-
1308+01.50 TO 1310+31.50	230.0	46.0	1175.6	117.6	2.4	-	98.7	-	49.4	-	1175.6	-	-	15.5	-	-
1310+31.50 TO 1312+31.50	200.0	52.0	1155.6	115.6	2.3	-	97.1	-	48.5	-	1155.6	-	-	13.5	-	-
1312+31.50 TO 1312+90.00	58.5	55.0	357.5	35.8	0.7	-	30.0	-	15.0	-	357.5	-	-	3.9	-	-
1312+90.00 TO 1321+62.30	872.3	40.0	3876.9	387.7	7.8	-	325.7	-	162.8	-	3876.9	-	-	58.9	-	-
1321+62.30 TO 1323+92.30	230.0	46.0	1175.6	117.6	2.4	-	98.7	-	49.4	-	1175.6	-	-	15.5	-	-
1323+92.30 TO 1325+93.30	201.0	52.0	1161.3	116.1	2.3	-	97.6	-	48.8	-	1161.3	-	-	13.6	-	-
1325+93.30 TO 1326+50.00	56.7	55.0	346.5	34.7	0.7	-	29.1	-	14.6	-	346.5	-	-	3.8	-	-
1326+50.00 TO 1334+75.50	825.5	40.0	3668.9	366.9	7.3	-	308.2	-	154.1	-	3668.9	-	-	55.7	-	-
1334+75.50 TO 1337+05.50	230.0	46.0	1175.6	117.6	2.4	-	98.7	-	49.4	-	1175.6	-	-	15.5	-	-
1337+05.50 TO 1339+05.00	199.5	52.0	1152.7	115.3	2.3	-	96.8	-	48.4	-	1152.7	-	-	13.5	-	-
1339+05.00 TO 1339+62.00	57.0	54.0	342.0	34.2	0.7	-	28.7	-	14.4	-	342.0	-	-	3.8	-	-
1339+62.00 TO 1349+49.50	987.5	40.0	4388.9	438.9	8.8	-	368.7	-	184.3	-	4388.9	-	-	66.7	-	-
1349+49.50 TO 1351+79.50	230.0	45.0	1150.0	115.0	2.3	-	96.6	-	48.3	-	1150.0	-	-	15.5	-	-
1351+79.50 TO 1353+79.50	200.0	50.0	1111.1	111.1	2.2	-	93.3	-	46.7	-	1111.1	-	-	13.5	-	-
1353+79.50 TO 1354+42.50	63.0	44.0	308.0	30.8	0.6	-	25.9	-	12.9	-	308.0	-	-	4.3	-	-
1354+42.50 TO 1366+01.00	1158.5	40.0	5148.9	514.9	10.3	-	432.5	-	216.3	-	5148.9	-	-	78.2	-	-
1366+01.00 TO 1366+98.00	97.0	46.0	495.8	49.6	1.0	-	41.6	-	20.8	-	495.8	-	-	6.5	-	-
1366+98.00 TO 1369+78.00	280.0	52.0	1617.8	161.8	3.2	-	135.9	-	67.9	-	1617.8	-	-	18.9	-	-
1369+78.00 TO 1370+08.00	30.0	65.0	216.7	21.7	0.4	-	18.2	-	9.1	-	216.7	-	-	2.0	-	-
1370+08.00 TO 1370+98.00	90.0	100.0	1000.0	100.0	2.0	-	84.0	-	42.0	-	1000.0	-	-	6.1	-	-
1370+98.00 TO 1371+31.00	33.0	137.0	502.3	50.2	1.0	-	42.2	-	21.1	-	502.3	-	-	2.2	-	-
1371+31.00 TO 1371+85.00	54.0	63.0	378.0	37.8	0.8	-	31.8	-	15.9	175.0	378.0	-	-	3.6	-	48.6
1371+85.00 TO 1375+89.00	404.0	40.0	1795.6	179.6	3.6	-	150.8	-	75.4	-	1795.6	-	-	27.3	-	-
1375+89.00 TO 1378+00.00	211.0	46.0	1078.4	107.8	2.2	-	90.6	-	45.3	-	1078.4	-	-	14.2	-	-
1378+00.00 TO 1379+14.00	114.0	52.0	658.7	65.9	1.3	-	55.3	-	27.7	-	658.7	-	-	7.7	-	-
1379+14.00 TO 1379+59.00	45.0	52.0	260.0	26.0	0.5	-	21.8	-	10.9	-	-	-	260	3.0	-	-
1379+59.00 TO 1380+30.00	71.0	52.0	410.2	34.2	0.7	-	28.7	-	14.4	-	-	342.1	-	4.8	-	-
1380+30.00 TO 1380+97.00	67.0	57.5	428.1	9.1	0.2	-	7.7	-	3.8	-	-	91.3	-	4.5	-	46.9
1380+97.00 TO 1381+20.30	23.3	47.5	123.0	8.6	0.2	-	7.2	-	3.6	-	-	86.1	-	1.6	-	-
1381+20.30 TO 1383+92.00	271.7	24.0	724.5	72.5	1.4	-	60.9	-	30.4	-	-	724.5	-	-	-	24.0
TOTALS	13820	2397	64902	6446	129	0	5414	0	2708	510	62956	1244	260	914	0	213

• COLES/CUMBERLAND

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVING SCHEDULE RIGHT SECTION (NB)				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\swartzw\dms50699\shch_74157.dgn		DRAWN -	REVISED -		SCALE: N/A	SHEET NO.	OF SHEETS	STA.	TO STA.	824	(16-2.19X-2)RS-1.19B.198R	52	19
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -						CONTRACT NO. 74157				
PLOT DATE = 10/17/2008		DATE -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				